


LCDOT PLAT GUIDELINES

- Plat of Highways LCDOT Checklist
- Example Legal Description
- LCSMC Restrictive Covenant Language for Plats
- Lake County Recorder's Office Guidelines
- Exhibit



PLAT OF HIGHWAYS & LEGAL DESCRIPTION CHECKLIST

REVISED 3/10/2017

A copy of this initialed and dated checklist shall be submitted to Lake County Division of Transportation along with the Plats of Highway and Legal Descriptions.

	<u>Initials or N/A</u>	<u>Date</u>
1. Plat of Highways sheet size is 22" x 34".	_____	_____
2. A project cover sheet is required.	_____	_____
3. All lettering should be 1/10 th inch or greater.	_____	_____
4. Complete the project box in the lower right-hand corner.	_____	_____
5. Show survey company name, address and/or logo (if applicable) above the title box.	_____	_____
6. Show North Arrow, up or to the right and appropriate scale bar on each page.	_____	_____
7. Coordinates for all projects should be based on Illinois State Plane Coordinate System, East zone, NAD83 (Adjustment). The referenced NGS monumentation should be noted on the plat.	_____	_____
8. Plat will include the following notes:	_____	_____
• Bearings and distances shown hereon reference the Illinois State Plane Coordinate System, East Zone, North American Datum of 1983 (adjustment year) "grid". NOTE: added "grid" for those who look at the plats, such as appraisers, and are not aware that state plane and grid are synonymous and it ties into the next statement.		
• All measured and calculated distances are "grid" not "ground". To obtain ground distances, divide grid distances shown by the combination factor of 0.999999.		
• Areas shown on this plat are "ground".	_____	_____
9. Label the Section, Township, Range, Principal meridian and County at the top of each applicable sheet.	_____	_____
10. Label all subdivisions, (incl. recording date and document number), blocks, and lots on the plat of highways.	_____	_____
11. All known recording dates and document numbers (subdivision, right-of-way, deed, etc.) will be included in the legal descriptions.	_____	_____
12. Show all section/quarter section corners and ties on the Plat of Highway. These should relate to the ties on the corresponding monument records. Label the monument recording date and document number.	_____	_____
13. Show necessary land lines with proper line types (section lines, lot lines, property lines, etc.)	_____	_____
14. Indicate and label the following lines (use the proper IDOT line types):		
• Existing and proposed right-of-way lines (use the proper line types)		
• Existing and proposed access control lines		
• Existing roadway easements lines and proposed easement lines	_____	_____
15. Show width of existing right-of way at least once per sheet.	_____	_____

16. Reference the documents which established the existing right-of-way or "As monumented and occupied" on the plat of highway.

17. **Acquiring Fee to Dedicated Right of Way**

Obtain the fee interest in right of way. When the owner has a fee interest to dedicated right of way that is adjacent to the property, the fee interest is acquired for that portion of the right of way which lies between the existing right of way line and the property line. This would be in addition to any new right of way required. This procedure will eliminate the owner from having to pay taxes on the dedicated right of way and will make it easier for utility companies to obtain permits.

18. Show all distances and bearings as used in the legal descriptions.

19. Show the radius (R), length (L), chord length (CH) and chord bearing (CB) for all curves as used in the legal descriptions (Use curve tables as applicable).

20. Label the Point of Commencing (P.O.C.) and Point of Beginning (P.O.B.) for every parcel when applicable.

21. Total holding property (including contiguous property) should be shown and labels (bearings, distances, angles, etc.) will be identical to the title report legal description.

22. Use land hooks to show common lines of ownership for contiguous property.

23. The property line symbol should be shown on all sides of the total holding parcel.

24. Indicate any land locked remainders.

25. Parcel numbers are to be shown as four (4) digits and boxed in a rectangle. Use the suffix "PE" for Permanent easement "TE" for temporary easement and "AC" for access control. No suffix is needed for a parcel being conveyed.

26. Areas shall be shown to the nearest 0.001 Acre. All parcels 0.010 of an acre or less should also be shown to the nearest square foot.

27. Complete the Parcel Table:

- Parcel Number
- Total Holdings Acres
- Part Taken Acres (Include Square Feet when 0.010 of an acre or less)
- Areas in existing R.O.W. Acres (prescription, monumented, occupied or common law)
- Remainder Area Acres
- Easement Area Acres (Include Square Feet when 0.010 of an acre or less)
- Parcel Index Number (List all P.I.N.'s for the total holdings)

28. Complete the Index Table on cover or as 2nd sheet if too many parcels for cover:

- Parcel Number
- Owners' Name (as listed in the title commitment)
- Sheet Number
- Property Acquired By

29. Legal Description Heading to be on right side & on each sheet:

- Route
- Section
- County
- Parcel Number
- Beginning to ending station (Both stations should be from same center line)
- Parcel Index Number (List only P.I.N.'s for the affected parcel)

- | | | | |
|-----|---|--|--|
| 30. | Legal Descriptions will include the following: | | |
| | <ul style="list-style-type: none"> • CAPTION FORMAT: "... In (Name) County, Illinois, bearings and distances Based on the Illinois State Plane Coordinate System, East Zone, NAD83 (Adjustment year), with a combined factor of _____", described as follows..." • ...BODY OF LEGAL... • END WITH AREA STATEMENT: Said parcel Containing X.XXX acres, more or less, of which X.XXX acres, more or less, was previously dedicated or used for highway purposes. | | |
| 31. | The type and use of all buildings on the total holding should be indicated. | | |
| | <ul style="list-style-type: none"> • All buildings within 100 feet of the proposed right-of-way or easement should be dimensioned and tied perpendicular to the proposed right-of-way. • All buildings beyond 100 feet from the proposed right-of-way or easement should just be outlined on the plat. | | |
| 32. | Show and label all private improvements in the proposed/existing Right-of-Way and proposed easement lines in the parcel. This includes fences, signs, light standards, private utilities, canopies, driveways, parking lots, etc. | | |
| 33. | Show all fuel pump islands with perpendicular ties to the proposed right-of-way or proposed easements. | | |
| 34. | Show all encroachments within the existing right of way.
(This would include parking areas) | | |
| 35. | Label the route and street name designation once per sheet. | | |
| 36. | Label the project's beginning and ending stations | | |
| 37. | Show the proposed centerline and label with IDOT stationing for State highways and LCDOT stationing for County highways, including all station equations. | | |
| 38. | Label the station and offset at the following points: | | |
| | <ul style="list-style-type: none"> • All proposed take and easement corners. • Intersection of all property lines with the proposed right-of-way lines and easement lines. | | |
| 39. | The station of the intersection of the proposed centerline with all Section and Quarter Section lines should be shown. | | |
| 40. | The bearing and distance of all section and quarter section lines measured for the project shall be shown. | | |
| 41. | Show all found monumentation with reference to true corner location. (Note: Following the completion of construction, all property corner monumentation found where new R.O.W. was not acquired shall be verified to still be in place. Any property corner monumentation destroyed within project limits during construction is to be replaced in the previously located positions. This will be coordinated with the Resident Engineer). | | |
| 42. | Show all set monumentation. (Note: Monumentation for proposed R.O.W. is to be placed after completion of construction in areas that may be disturbed during construction, e.g., temporary construction easements. The consultant will be notified by the Resident Engineer). | | |

43. List in tabular form the state plane coordinates for:
- All centerline and/or survey baseline control points
 - P.C., P.I., P.T.
 - Station equations
 - Project begin and project end points
 - Proposed right of way monuments
 - All found monumentation within project limits
 - All section/quarter section corners utilized.

Provide header for coordinate table text box (see below).

<p style="text-align: center;">PROJECT COORDINATES Illinois State Plane, East Zone, NAD 83 (Adjustment Year)</p>
--

44. Provide legend for all symbols and abbreviations used on plat. _____
45. If a proposed take is in a recorded subdivision, any easements or setback lines shown on the recorded plat that affect the subject parcel are to be shown. _____
46. All plat sheets shall include the following statement and signature block for the County Engineer, revised with the Lake County Engineer's name and the appropriate County Highway number(s): _____

STATE OF ILLINOIS)
)SS
COUNTY OF LAKE)

I, **County Engineer's Name**, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY **XX** IN SAID COUNTY.

DATED THIS ____ DAY OF _____ 20__ A.D.

COUNTY ENGINEER

- Items 47 and 48 shall be completed after initial approval.
47. Monument Record Documents should be prepared and recorded for Section/Quarter Section corners utilized for which no Monument Record exists. New Monument Records should be prepared and recorded for those documents which show ties within the proposed right-of-way. _____
48. Submit one complete set of signed and sealed mylars, a MicroStation file (.dgn), a .pdf file of the signed Plat of Highways, and the legal descriptions in Microsoft Word format and in a .pdf file. _____

Route : Old McHenry Road (County Highway 32)
Section: 11-00083-09-RS
County : Lake
Job No.:
Parcel : 0003-A
Sta. 15+40.18 To Sta. 15+73.00

Index No. 15-30-100-019

That part of the Northwest Quarter of Section 30, Township 43 North, Range 11 East of the Third Principal Meridian, in Lake County, Illinois, bearings and distances are based on the Illinois Coordinate System, NAD 83(2011) East Zone, with a combination factor of 0.9999548166, described as follows:

Commencing at the southeast corner of Lot 2 in Fannings Subdivision, being a subdivision of part of the Northwest Quarter of Section 30, Township 43 North, Range 11 East of the Third Principal Meridian, according to the plat thereof recorded August 1, 1962 as document number 1157511, being also a point on the center line of Old McHenry Road recorded November 17, 1942 as document number 521242; thence on an Illinois Coordinate System NAD 83(2011) East Zone bearing of South 60 degrees 16 minutes 50 seconds East along the said center line of Old McHenry Road, a distance of 222.29 feet to the point of beginning; thence North 29 degrees 43 minutes 10 seconds East, a distance of 40.00 feet to the northeasterly right of way line of Old McHenry Road recorded November 27, 1942 as document number 521617; thence North 64 degrees 01 minute 37 seconds East, a distance of 12.11 feet to the east line of the grantor according to special warranty deed recorded September 4, 2014 as document number 7128488; thence South 2 degrees 14 minutes 50 seconds West along the east line of the grantor according to said special warranty deed, a distance of 56.35 feet to the said center line of Old McHenry Road; thence North 60 degrees 16 minutes 50 seconds West along the said center line of Old McHenry Road, a distance of 32.82 feet to the point of beginning.

Said parcel containing 0.022 acre, more or less, of which 0.021 acre, more or less, was previously dedicated or used for highway purposes.

Example

The following are examples of legal descriptions when extending the right of way to the centerline of the road.

LEGAL DESCRIPTION - PARCEL 003

That part of the Northeast Quarter of Section 31, Township 46 North, Range 10 East of the Third Principal Meridian described as follows: Commencing at the northeast corner of said Northeast Quarter; thence South 0 degrees 23 minutes 30 seconds East, 40.00 feet along the east line of said Northeast Quarter; thence South 89 degrees 27 minutes 46 seconds West, 148.00 feet along a line parallel with and 40.00 feet south of the north line of said Northeast Quarter to the west line of the east 148.00 feet of said Northeast Quarter for the Point of Beginning; thence continuing South 89 degrees 27 minutes 46 seconds West, 213.51 feet to the west line of land described in Document No. 5720634 recorded January 20, 2005; thence North 0 degrees 23 minutes 30 seconds West, 40.00 feet along said west line to the north line of said Northeast Quarter; thence North 89 degrees 27 minutes 46 seconds East, 213.51 feet along said north line to the west line of the east 148.00 feet of said Northeast Quarter; thence South 0 degrees 23 minutes 30 seconds East, 40.00 feet along said west line to the Point of Beginning, all in Lake County, Illinois. Said parcel contains 0.196 acres more or less, of which 0.162 acres more or less have been previously used or dedicated.

LEGAL DESCRIPTION - PARCEL 004

That part of the Northeast Quarter of Section 31, Township 46 North, Range 10 East of the Third Principal Meridian described as follows: Beginning at the northeast corner of said Northeast Quarter; thence South 0 degrees 23 minutes 30 seconds East, 40.00 feet along the east line of said Northeast Quarter; thence South 89 degrees 27 minutes 46 seconds West, 148.00 feet along a line parallel with and 40.00 feet south of the north line of said Northeast Quarter to the west line of the east 148.00 feet of said Northeast Quarter; thence North 0 degrees 23 minutes 30 seconds West, 40.00 feet along said west line to the north line of said Northeast Quarter; thence North 89 degrees 27 minutes 46 seconds East, 148.00 feet along the north line of said Northeast Quarter to the Point of Beginning, all in Lake County, Illinois. Said parcel contains 0.136 acres more or less, of which 0.112 acres more or less have been previously used or dedicated.

Example

STATE OF ILLINOIS)
) SS:
COUNTY OF LAKE)

STORMWATER/DRAINAGE RESTRICTIVE COVENANT BY DEED

_____, fee owner of the following described real property located in the
_____, County of Lake, State of Illinois, being the owner of all
that certain real estate designated and described as follows,

[Legal Description]

said parcel(s)/lot(s) to be subject to the following covenants:

1. **Use Restriction.** A restrictive covenant running with the land for the installation and maintenance of stormwater and drainage facilities are reserved on the following described property:

[Legal Description of Restrictive Covenant Area]

Within these restricted areas, no structure, planting, or other material shall be placed or permitted to remain which may damage or interfere with the installation or performance of stormwater and drainage facilities, floodplain, wetlands & buffer areas or which may change the direction of flow of stormwater or drainage channels in the restricted areas, or which may obstruct or retard the flow of water through stormwater and drainage channels in the restricted area. The restricted area of each lot shall be maintained continuously by the owner of the parcel or lot.

2. **Term.** This covenant is to run with the land and shall be binding on all parties and their successors and all persons claiming under them, and all public agencies, for a perpetual period from the date these covenants are recorded.
3. **Enforcement.** Enforcement shall be by proceedings at law or in equity against any person violating or threatening to violate any covenant either to restrain violation or to recover damages. Enforcement may be undertaken by any grant or grantee in the chain of title, any property owner lying downstream or upstream adversely affected by any violation or threat to violate this covenant, or the host municipality or stormwater management commission.
4. **Reference.** This restrictive covenant shall be referenced on all deeds or other future instruments of conveyance for the subject parcel(s)/lot(s).

In Witness Whereof _____, the fee owner, has

caused these presents to be signed and acknowledged, this _____ day of
_____, 2_____.

By: _____

STATE OF ILLINOIS)

) SS:

COUNTY OF LAKE)

STORMWATER/DRAINAGE RESTRICTIVE COVENANT BY PLAT

_____, fee owner of the following described real property located in the _____, County of Lake, State of Illinois, such property being the real property now duly platted as _____, as such plat is now recorded as Document No. _____, in the office of the Recorder of Deeds of the County of Lake, State of Illinois, makes the following declarations as to limitations, restrictions and uses to which those areas designated as stormwater & drainage ways or floodplain wetland & buffer areas in said parcel/subdivision may be put, and specifies that such declarations shall constitute covenants to run with all the land, as provided by law, and shall be binding on all parties and their successors, and all persons claiming under them, and for the benefit of and limitations on all future owners in such parcel/subdivision and the surrounding and downstream and upstream areas, this declaration being in compliance with applicable stormwater and drainage rules, regulations, and ordinances, and suitable for such stormwater retention and drainage pathways and facilities, as specified herein:

1. **Use Restriction.** A restrictive covenant running with the land for the installation and maintenance of stormwater and drainage floodplain wetlands & buffer areas are reserved as shown on the recorded plat. Within these restricted areas, no structure, planting, or other material shall be placed or permitted to remain which may damage or interfere with the installation or performance of stormwater and drainage floodplain wetland & buffer areas, or which may change the direction of flow of stormwater or drainage channels in the restricted areas, or which may obstruct or retard the flow of water through stormwater and drainage channels in the restricted area. The restricted area of each lot shall be maintained continuously by the owner of the lot, except for those improvements for which a public authority or a homeowners association has formally accepted responsibility.

2. **Term** This covenant is to run with the land and shall be binding on all parties and their successors and all persons claiming under them, and all public agencies, for a perpetual period from the date these covenants are recorded.
3. **Enforcement.** Enforcement shall be by proceedings at law or in equity against any person violating or threatening to violate any covenant either to restrain violation or to recover damages. Enforcement may be undertaken by any grantor or grantee in the chain of title, any property owner in the subdivision, any property owner lying downstream or upstream adversely effected by any violation or threat to violate this covenant, or the host municipality or stormwater management commission.
4. **Reference.** This restrictive covenant shall be referenced on all deeds or other instruments of conveyance for all lots or parcels in said _____ subdivision.

In Witness Whereof _____, the fee owner, has caused these presents to be signed and acknowledged, this _____ day of _____, 2_____.

By: _____

SMC EXAMPLE

[illegible]

WETLAND AND WETLAND BUFFER RESTRICTIVE COVENANT BY DEED

_____, fee owner of the following designated and described real property located in the [Name of Subdivision, if applicable], [City or Village], County of Lake, State of Illinois:

[Legal Description]

hereby makes the following declarations as to limitations, restrictions and uses to which those areas designated as WETLAND and WETLAND BUFFER in said property may be put, and specifies that such declarations shall constitute covenants to run with all the land, as provided by law, and shall be binding on all parties and their successors, and all persons claiming under them, and for the benefit of and limitations on all future owners of said property and the surrounding and downstream and upstream areas, this declaration being in compliance with applicable wetland regulations, stormwater and drainage rules, and ordinances as specified herein:

1. Purpose. The purpose of this restrictive covenant is to perpetually preserve the wetland(s) and associated buffer(s) in their natural condition. Specifically, this covenant will serve to protect the wetland and buffer areas identified in the permit documents **[REFERENCE LAKE COUNTY WATERSHED DEVELOPMENT PERMIT # and/or U.S. ARMY CORPS OF ENGINEERS PERMIT #]**.
2. Prohibited Actions. Any activity on, or use of, the wetland and buffer that is inconsistent with the purpose of this covenant is expressly prohibited. By way of example, but not by way of limitation, the following activities and uses are explicitly prohibited:
 - i. Division. Any division or subdivision of the wetland and buffer areas is prohibited.
 - ii. Commercial Activities. Any commercial activity on the wetland and buffer areas, except for passive recreational activity, is prohibited.
 - iii. Industrial Activities. Any industrial activity on the wetland and buffer areas is prohibited.
 - iv. Construction. The placement or construction of any human-made structure or feature on the wetland and buffer areas including, but not limited to, buildings, fences, roads, and parking lots is prohibited.
 - v. Vegetation. Any cutting, mowing, plowing, or removal of trees or other vegetation in the wetland and buffer areas is prohibited, except for the cutting or removal of trees which pose a threat to human life or property. Removal of non-native vegetation from the wetland and buffer areas is permitted, if conducted in accordance with an approved maintenance plan.
 - vi. Land Surface Alteration. Any alteration of the land surface in the wetland and buffer areas is prohibited, including, but not limited to, the placement of dredged or fill material, excavation, and grading. In addition, mining of any substance that must be quarried or removed by methods that will consume or deplete the surface estate, including, but not limited to, the removal of topsoil, sand, gravel,

rock, and peat, and exploring for, developing, and extracting oil, gas, hydrocarbons, or petroleum products are all prohibited activities in the wetland and buffer areas.

- vii. Utilities. Unless included as part of the permitted plans, no underground or overhead utility lines shall be allowed in the wetland and buffer areas, including, but not limited to sewer, water, electrical, gas, telephone, and cable television. Existing lines may remain, but any proposed maintenance work requiring intrusion into wetland and buffer areas shall require prior written authorization from the Lake County Stormwater Management Commission ("SMC"), except for emergency repair of utility lines that pose a threat to human health and safety.
 - viii. Dumping. Waste, debris, and unsightly or offensive material is not allowed and may not be accumulated on the wetland and buffer areas.
 - ix. Water Courses. Natural water courses, lakes, wetlands, or other bodies of water may not be altered.
 - x. Off-Road Recreational Vehicles. Motorized off-road vehicles including, but not limited to, snowmobiles, dune buggies, all-terrain vehicles, and motorcycles may not be operated on the wetland and buffer areas, except on designated trails shown on the permitted plans.
 - xi. Signs and Billboards. Billboards are prohibited. Signs are prohibited, except the following signs may be displayed to specifically state: 1) The name and address of the property or the owner's name; 2) the area is a protected wetland/conservation area; 3) prohibition of any unauthorized entry or use; or 4) an advertisement for the sale or rent of the Property.
3. Term. This covenant is to run with the land and shall be binding on all parties and their successors and all persons claiming under them, and all public agencies, for perpetuity from the date these covenants are recorded.
4. Enforcement. Enforcement shall be by proceedings at law or in equity against any person violating or threatening to violate any covenant either to restrain violation or to recover damages. Enforcement may be undertaken by any grantor or grantee in the chain of title, any adjoining property owner, any property owner lying downstream or upstream adversely effected by any violation or threat to violate this covenant, the host municipality, the SMC, or the U.S. Army Corps of Engineers ("USACE").
5. Reference. This restrictive covenant shall be referenced on the deed or other instruments of conveyance for said property.

In Witness Whereof _____, the fee owner, has caused these presents to be signed and acknowledged, this _____ day of _____, 2_____.

By: _____

SMC EXAMPLE

[illegible]

WETLAND AND WETLAND BUFFER RESTRICTIVE COVENANT BY PLAT

_____, fee owner of the following described real property located within the Village/City of _____, County of Lake, State of Illinois, such property being the real property now duly platted as _____, as such plat is now recorded as Document No. _____, in the office of the Recorder of Deeds of the County of Lake, State of Illinois, hereby makes the following declarations as to limitations, restrictions and uses to which those areas designated as “WETLAND” and “WETLAND BUFFER” in said parcel/subdivision may be put, and specifies that such declarations shall constitute covenants to run with all the land, as provided by law, and shall be binding on all parties and their successors, and all persons claiming under them, and for the benefit of and limitations on all future owners in such parcel/subdivision and the surrounding and downstream and upstream areas, this declaration being in compliance with applicable stormwater and drainage rules, regulations, and ordinances as specified herein:

1. Purpose. The purpose of this restrictive covenant is to perpetually preserve the wetland(s) and associated buffer(s) in their natural condition. Specifically, this covenant will serve to protect the wetland and buffer areas identified in the permit documents **[REFERENCE LAKE COUNTY WATERSHED DEVELOPMENT PERMIT # and/or U.S. ARMY CORPS OF ENGINEERS PERMIT #]**.
2. Prohibited Actions. Any activity on, or use of, the wetland and buffer that is inconsistent with the purpose of this covenant is expressly prohibited. By way of example, but not by way of limitation, the following activities and uses are explicitly prohibited:
 - i. Division. Any division or subdivision of the wetland and buffer areas is prohibited.
 - ii. Commercial Activities. Any commercial activity on the wetland and buffer areas, except for passive recreational activity, is prohibited.
 - iii. Industrial Activities. Any industrial activity on the wetland and buffer areas is prohibited.
 - iv. Construction. The placement or construction of any human-made structure or feature on the wetland and buffer areas including, but not limited to, buildings, fences, roads, and parking lots is prohibited.
 - v. Vegetation. Any cutting, mowing, plowing, or removal of trees or other vegetation in the wetland and buffer areas is prohibited, except for the cutting or removal of trees which pose a threat to human life or property. Removal of non-native vegetation from the wetland and buffer areas is permitted, if conducted in accordance with an approved maintenance plan.
 - vi. Land Surface Alteration. Any alteration of the land surface in the wetland and buffer areas is prohibited, including, but not limited to, the placement of dredged or fill material, excavation, and grading. In addition, mining of any substance that must be quarried or removed by methods that will consume or deplete the surface estate, including, but not limited to, the removal of topsoil, sand, gravel,

rock, and peat, and exploring for, developing, and extracting oil, gas, hydrocarbons, or petroleum products are all prohibited activities in the wetland and buffer areas.

- vii. Utilities. Unless included as part of the permitted plans, no underground or overhead utility lines shall be allowed in the wetland and buffer areas, including, but not limited to sewer, water, electrical, gas, telephone, and cable television. Existing lines may remain, but any proposed maintenance work requiring intrusion into wetland and buffer areas shall require prior written authorization from the Lake County Stormwater Management Commission ("SMC"), except for emergency repair of utility lines that pose a threat to human health and safety.
 - viii. Dumping. Waste, debris, and unsightly or offensive material is not allowed and may not be accumulated on the wetland and buffer areas.
 - ix. Water Courses. Natural water courses, lakes, wetlands, or other bodies of water may not be altered.
 - x. Off-Road Recreational Vehicles. Motorized off-road vehicles including, but not limited to, snowmobiles, dune buggies, all-terrain vehicles, and motorcycles may not be operated on the wetland and buffer areas, except on designated trails shown on the permitted plans.
 - xi. Signs and Billboards. Billboards are prohibited. Signs are prohibited, except the following signs may be displayed to specifically state: 1) The name and address of the property or the owner's name; 2) the area is a protected wetland/conservation area; 3) prohibition of any unauthorized entry or use; or 4) an advertisement for the sale or rent of the Property.
3. Term. This covenant is to run with the land and shall be binding on all parties and their successors and all persons claiming under them, and all public agencies, for perpetuity from the date these covenants are recorded.
4. Enforcement. Enforcement shall be by proceedings at law or in equity against any person violating or threatening to violate any covenant either to restrain violation or to recover damages. Enforcement may be undertaken by any grantor or grantee in the chain of title, any property owner in the subdivision, any property owner lying downstream or upstream adversely effected by any violation or threat to violate this covenant, the host municipality, the SMC, or the U.S. Army Corps of Engineers ("USACE").
5. Reference. This restrictive covenant shall be referenced on the deed or other instruments of conveyance for said property.

In Witness Whereof _____, the fee owner, has caused these presents to be signed and acknowledged, this _____ day of _____, 2_____.

By: _____

PLATS

Guidelines for Recording

The following guidelines based on statutory requirements are offered to help in the preparation, execution and recordation of various plats. It is my hope as Lake County Recorder, that these guidelines are helpful to our customers and landowners. Should you have additional questions or need further clarification, please do not hesitate to contact my office at (847) 377-2575. We look forward to serving you with courtesy and efficiency!



Lake County RECORDER OF DEEDS
18 N County St – 6th Floor
Waukegan, IL 60085-4358

Phone: (847) 377-2575
Fax: (847) 984-5860
e-mail: recorder@lakecountyil.gov
website: www.lakecountyil.gov/recorder

TABLE OF CONTENTS

TOPIC	PAGE
Subdivision of Land.....	3
Recording Requirements Checklist	3
General Plat Requirements	4
Owner's Certificate.....	5
Recorder's Certificate.....	5
Surveyor's Certificate	6
Municipal Certificates	7
County Certificates.....	7
Condominium Plat & Declaration	8
General Condominium Plat Recording Requirements	8
Condominium Declaration	8
Recording Requirements for Amendment to a Declaration for Condominium	9
Recording Requirements for Amendment that Adds Units	9
Dedication Plat (Also applies to dedication of right of way).....	10
Recording Requirements for Dedication Plats	10
Plat of Dedication to the County of Lake for Road Purposes	11
Vacation Plat.....	13
Vacating of Streets and Alleys	13
Recording Requirements for Vacations (excluding vacation of easement).....	15
Annexation/Disconnection Plat.....	16
Recording Requirements for Annexations/Disconnections.....	17
Plat Certificate of Amendment / Plat Certificate of Correction.....	18
Samples and Exhibits.....	19
Samples of Surveyor's Certificates	20
Sample School District Certificate.....	21
Sample County Highway Signature Certificates.....	22
Plat Act Affidavit	23
Request for Consolidation or Division of Tax Parcels	24
Important Information About Dividing Property For Tax Purposes	26
Schedule of Fees	27

Subdivision of Land

Illinois Compiled Statutes Ch. 765 Act 205

Whenever the owner of land subdivides it into 2 or more parts, any of which is less than 5 acres, he must have it surveyed and a subdivision plat thereof made by an Illinois Registered Land Surveyor. If any city, village or town has adopted an official plan, or part thereof, the plat of land situated within the area affected thereby must conform to the official plan or part thereof. (Requirements apply to Plats of Resubdivision, Planned Unit Developments and Consolidations as well.)

No subdivision plat is required in the instances outlined per the Plat Act Affidavit (see attachment), however the completed Plat Act Affidavit must be recorded with the deed.

Recording Requirements Checklist

- Is the plat an original between 8½" x 14" and 30" x 36"? (pg. 4)
- Has the Surveyor authorized another party to record the plat by a statement with his original signature and seal? (May be on a separate piece of paper, but must include the surveyor's original signature and seal.) (pg.4)
- Does the plat contain the name and address of the party submitting the recording? (pg. 4)
- Does plat have a mail-to address specified? (pg. 5)
- Has the Surveyor signed and sealed the plat after completing the legal description, a description of public ways and utilities, a certificate stating the location of the property within a municipality or the county, FEMA certification, and Department of Natural Resources approval? (pg. 6)
- Has the owner, his representative, or a Trust Officer signed the plat and included the printed name and address of the signer? (pg. 5)
- Has the owner, his representative, or a Trust Officer signature been notarized and the notary seal affixed? (pg. 5) (All owners must be notarized.)
- Has the owner submitted the School District Certificate? (not applicable for Plats of Resubdivision, Planned Unit Developments or Consolidations) (May be on a separate piece of paper, but must include the owner's signature(s) and must be notarized.) (pg. 5)
- Have the municipal corporate authorities approved the plat and indicated same by signatures, date and seals? (pg. 7)
- Has the municipal collector signed off on the plat? (Not necessary for property in unincorporated Lake County.) (pg. 7)
- Has the county plat officer approved the plat and signed and sealed it? (Only for property in unincorporated Lake County.) (pg. 7)
- Has LCDOT or IDOT signed and sealed the plat? (applies to plats with applicable roads) (pg. 7)
- Has the county clerk certified tax payment and signed and sealed the plat? (pg. 7)

General Plat Requirements

1. Plats must measure at least 8½" x 14", but no larger than 30" x 36".
2. We suggest additional copies be submitted at the time of recording for the customer's use. The Recorder's Office can provide copies at the time of recordation for a fee of \$5.00 per page.
3. Plats containing blank or illegible signature certificates will not be accepted for recording.
4. Plats of Subdivision, Resubdivision, Planned Unit Developments or Consolidations must be presented for recording by the Registered Land Surveyor who signed and sealed the plat. The surveyor may designate another party to submit the plat for recording on a certificate on the plat or by a separate letter. This designation must include the original surveyor signature and seal.
5. All plats must contain the name and address of the person actually submitting the plat for recording.
6. The names of all persons signing the plat must be typed or printed under or next to each signature except for notaries, as the notary seal is sufficient. The notary seal must be readable so the expiration date can be confirmed.
7. Corporate and municipal seals should be affixed to the plat where applicable.
8. *Note:* The Recorder's Office assumes that all statutory requirements enforced by the municipality and/or county have been met as verified by the approval and signatures of the municipal and/or county officers.
9. Plats of Consolidation are referenced in the Lake County Unified Development Ordinance (UDO) and some municipal development ordinances to address the use of more than one parcel for development purposes. Plats of Consolidation must meet all the requirements of a Plat of Resubdivision and should be renamed to reflect the new identity of the consolidation.

Public Act 92-0361 effective 1/1/02 provides that a plat of consolidation is exempt from municipal approval if the sole purpose of the consolidation is to bring a non-conforming parcel into conformance with local zoning requirements. The county must notify all municipalities located within 1 ½ miles of the subject property within 10 days after receiving a request. This exemption does not apply for an area in excess of 10 acres or to any consolidation that results in a plat of more than 10 individual lots flowing the consolidation.

Consolidations for combining tax parcels for tax purposes can be made by written request of the property owner to the Map Services Department. This type of consolidation does not change the underlying lot numbers in the subdivision. To create

a new lot of record, a Plat of Subdivision or Plat of Resubdivision should be prepared and named - for example, Plat of Subdivision - Smith Consolidation. (Rev. 12/15/97)

10. Plats of Survey and Highway Plats will be accepted for recording and indexed by property owner name. Additional signature certificates are not required. A clear designation of the owner, highway or property name will facilitate indexing and retrieval of the plat. (Rev. 12/31/97)
11. Mail-to name and address are required.

Owner's Certificate

1. The plat must contain a signature certificate with original signatures of the landowner or a representative of the owner.
2. If the property is owned under a Trust, the Trust Officer signature and seal of the bank (if available) must be included on the plat.
3. The name and address of the owner(s) or Trust Officer are to be printed under each signature.
4. The signature of the owner(s) must be acknowledged by a Notary Public and a legible seal for the notary stamped on the plat.
5. Public Act 90-286 (765 ILCS 205/1.005) requires when an owner is required to file a plat pursuant to Section 1 of the Plat Act, the owner shall submit simultaneously with the subdivision plat a notarized statement indicating to the best of the owner's knowledge, the school district in which each tract, parcel, lot or block lies. Can be a certificate on plat or separate paper. If statement included on plat, owner(s) signature and acknowledgement need not be provided twice. **(not applicable for Plats of Resubdivision or Consolidation)**

Recorder's Certificate

The Recorder's file stamp will indicate the date and time of recording and assign a document number.

Surveyor's Certificate

1. The plat must contain a complete legal description of the property being subdivided or resubdivided.
2. The plat must particularly describe and set forth all public streets, alleys, ways for public service facilities, ways for utility services and community antenna television systems, parks, playgrounds, school grounds or other public grounds, and all the tracts, parcels, lots or blocks, and numbering all such lots, blocks or parcels by progressive numbers, giving their precise dimensions. Additional topographical and profile studies may be prepared as subsidiary studies. (For further reference see 765 ILCS 205/1)
3. Surveyor's certificate must state if the land is or is not within any incorporated city, town or village, or within 1.5 miles of the corporate limits of any incorporated city, town or village which has adopted a city plan and is exercising the special powers authorized by Division 12 of Article 11 of the Illinois Municipal Code, as now or hereafter amended, and not included in any municipality. (See attached Samples of Surveyor's Certificates)
4. Surveyor's certificate must indicate whether any part of the land is located within a special flood hazard area as identified by the Federal Emergency Management Agency (FEMA).
5. Any land bordering on or including any public waters of the State must be approved by the Department of Natural Resources. Sample certificate:

Approved by the Department of Natural Resources of the State of Illinois insofar as this subdivision plat, showing lands bordering upon or including public waters of the State of Illinois, relates to the provisions of 615 ICLS 5/7, "An Act in relation to the regulation of rivers, lakes and streams of the State of Illinois" approved June 10, 1911, as mended, requiring review and approval by said Department as to the boundary line between private interests and public interests. Dated at Springfield, Illinois, this _day of _____, 2____

_____.

State of Illinois by its Department of Natural Resources

By: _____, Director

6. The original plat must contain the Surveyor's original signature and seal, which may either be printed or embossed/raised. (For further reference see 225 ILCS 330/15)

Municipal Certificates

1. The corporate authorities may provide by ordinance that any map, plat or subdivision of any block, lot, sub-lot, or part thereof, shall be submitted to the corporate authorities, or to some officer to be designated by them, for approval prior to being accepted for recording. (65 ILCS 5/11-15-1)

The municipality or county shall not approve the plat unless the topographical and profile studies to be submitted with the subdivision plat have on their face the signed statement of a Registered Professional Engineer, and the owner of the land or his duly authorized attorney, a statement re: the drainage of surface waters. The topographical and profile studies shall not be recorded but shall be retained and filed by the municipality or county.

Neither should the municipality or county approve a plat until the Illinois Department of Transportation, local highway authority, and or local health departments have provided written approval as needed.

2. Corporate approval must be indicated by the signature of the mayor/president and attested to by the municipal clerk with the date of approval included. Corporate approval signed by City Clerk only is acceptable as long as date of approval is listed.
3. Village seal must be applied/embossed.
4. Approval by a municipal Planning Commission may be indicated by the signature of the chair of said commission including the date of approval.
5. The municipal collector or other municipal representative must sign off attesting to any unpaid special assessments.

County Certificates

1. If county approval is required (based on description included in Surveyor's Certificate), the County Plat Officer must sign and seal the plat.
2. If the plat includes a County Highway, the Lake County Division of Transportation must sign the applicable certificate (see samples) allowing or prohibiting access (765 ILCS 205/2).
3. The County Clerk must certify that there are no delinquent general taxes, unpaid current general taxes, delinquent special assessments or unpaid current special assessments against any of the land included in the described property. The certificate must be signed and sealed by the County Clerk or an authorized staff member. (35 ILCS 200/9-55) A sample County Clerk certificate can be found on page 12.

Condominium Plat & Declaration

Illinois Compiled Statutes Ch. 765 Act 605/4-5

Condominium Plat - This is a plat of survey of the land parcel and all units in the property. The Condominium Plat shall consist of a horizontal and vertical delineation (drawing) of each unit. These unit drawings within the Condominium Plat must provide linear measurements and location of building improvements and/or structures located on the parcel. The unit drawing must also provide the elevations above and below and measurements of finished or unfinished interior surfaces of floors and ceilings; the measurements of finished or unfinished interior surfaces of all perimeter walls; locations of wall surfaces and/or unit boundaries with respect the exterior boundaries as projected upward. The plat (unit) drawings must also provide measurements of the perimeter boundaries of that part of the property which constitutes a unit or any part thereof. Each unit shall be identified on the plat by a distinguishing number or symbol.

General Condominium Plat Recording Requirements

1. Plats must measure at least 8½" x 14", but no larger than 30" x 36".
2. Plat must contain legal description and signature certificate from the Registered Land Surveyor as preparer of the plat including an original signature and the surveyor's seal.
3. Plat must contain floor and ceiling elevations of condominium units.
4. Each unit must be identified by number or symbol *as stated in the Declaration*.
5. 1 original Condominium Plat and Declaration and 3 copies of each must be provided to the Recorder's Office.

Condominium Declaration

The Condominium Plat must be filed simultaneously with the Declaration.

The contents of the Declaration are as follows:

- The legal description of the parcel.
- The legal description of each unit w/identifying number or symbol.
- The name of the condominium, including the word Condominium.
- The name of the city and county where the condominium is located.
- The percentage of ownership interest in each unit. (Must total 100%.)
- The Declaration must also have preparer's name.
- The Declaration must also have the mail-to information.
- Declaration must be signed, dated and notarized. (*Signed by owner, developer, declarant.*)

Please note that the Recorder's office assumes, where it is applicable, that all statutory requirements enforced by the county and/or the municipality have been met.

Recording Requirements for Amendment to a Declaration for Condominium

1 original and 3 copies required for the Recorder

Illinois Compiled Statutes Ch. 765 Act 605/17 & 25

- Legal description.
- Name of the Condominium.
- Document number of the original recorded Condominium.
- Reference in language to pages/exhibits being amended.
- Amendment must have preparer's name.
- Amendment must have the mail-to information.
- Amendment must be signed, dated and notarized. (*Signed by owner, developer, declarant.*)

Recording Requirements for Amendment that Adds Units

1 original and 3 copies required for the Recorder

Illinois Compiled Statutes Ch. 765 Act 605/17 & 25

- Name of the Condominium.
- Document number of the original recorded Condominium.
- Legal description of each unit w/identifying number or symbol.
- Percentage of ownership interest in each unit. (Must total 100%.)
- Amendment must have preparer's name.
- Amendment must have the mail-to information.
- Amendment must be signed, dated and notarized. (*Signed by owner, developer, declarant.*)
- Plat adding units have same requirements as original condominium plat.
- Plat must measure at least 8.5" x 14" but no more than 30" x 36".
- Plat must contain legal description and signature certificate from the Registered Land Surveyor as preparer of the plat including an original signature and the surveyor's seal.
- Plat must contain floor and ceiling elevations of condominium units.
- Each unit must be identified by number or symbol as stated in the Declaration.

Dedication Plat (Also applies to dedication of right of way)

Illinois Compiled Statutes Ch. 765 Act 205/3

The acknowledgement and recording of a plat of dedication, or the acknowledgement and the filing of the same shall be held in all courts to be a conveyance in fee simple of such portions of the premises platted as are marked or noted on such plat as donated or granted to the public, or any person, religious society, corporation, or body politic, and as a general warranty against the donor, his or her heirs and representatives, to such donee or grantee, for their use or for the use and purposes therein named or intended, and for no other use or purpose; and the premises intended for any street, alley, way, common or other public use in any city, village or town, or addition thereto, shall be held in the corporate name thereof in trust to and for the uses and purposes set forth or intended.

Recording Requirements for Dedication Plats

1. Plat must measure at least 8½" x 14", but no larger than 30" x 36".
2. As an instrument of conveyance, the name and address of the owner or owners to whom subsequent tax bills are to be sent shall be endorsed on the instrument. If eligible for tax exemption, an application for tax-exempt status on dedicated property is required through the Chief County Assessment Office.
3. The plat must contain a legal description and signature certificate from the Registered Land Surveyor as preparer including an original signature and surveyor's seal.
4. Metes and bounds descriptions must contain section, township and range with an identifiable point of beginning.
5. The plat must contain a signature certificate with original signatures of the land owner or representative of the owner.
6. The name and address of the owner must be printed under the signature.
7. The signature of the owner must be acknowledged by a Notary Public and a legible seal for the notary stamped on the plat.
8. Corporate approval (when applicable) must be indicated by the signature of the mayor/president/county chair and attested to by the municipal/county clerk including date of approval.
9. Village seal must be applied/embossed.
10. The attached guidelines apply to plats of dedication to the County of Lake for public road purposes. (Rev. 5/2/00)
11. The County Clerk must certify that there are no delinquent or current property taxes due, or outstanding special assessments. The certificate must be signed and sealed by the County Clerk or an authorized staff member.
12. The Recorder's file stamp will indicate the date and time of recording and assign a document number.
13. Mail-to name and address required.

Plat of Dedication to the County of Lake for Road Purposes

**PLEASE CONTACT LAKE COUNTY DIVISION OF TRANSPORTATION
FOR ADDITIONAL ASSISTANCE REGARDING THIS INFORMATION**

Heading:

PLAT OF DEDICATION
TO THE COUNTY OF LAKE
FOR
PUBLIC ROAD PURPOSES

Items Needed:

1. Legal Description (under heading)
2. Sketch showing old and new right of way, name of road and County Highway number
3. Right of way shall be designated as "HEREBY DEDICATED FOR PUBLIC ROAD PURPOSES."
4. PIN of property
5. Title report

Certificates Needed:

1. Certificates for property owner(s) stating that property has been surveyed and dedicated. Includes owner's address.
2. Notary Public Certificate
3. Mortgagee Certificate (if applicable)
4. County Clerk's Certificate (unpaid taxes – see below)
5. Collector's of Special Assessments Certificate (unpaid assessments)
6. Surveyor's Certificate
7. County Engineer's Certificate (see below)

Sample County Engineer's Certificate

STATE OF ILLINOIS
COUNTY OF LAKE

} SS

This dedication hereby accepted for public road purpose this ____ day of _____, _____

COUNTY ENGINEER

Sample Mortgage Subordination

_____ as the legal holder and owner of a mortgage dated _____ and recorded as document number _____ in _____ Lake County, Illinois, on _____ does hereby consent to and subordinate its interests in the property described in this Plat of Dedication to the County of Lake for Public Road Purposes. This subordination only applies to the portion of the mortgaged property dedicated for public road purposes and does not release the property owner from any of the obligations of the mortgage with respect to the remaining property.

Dated this _____ day of _____, _____

By: _____

Title: _____

Sample County Clerk's Certificate

STATE OF ILLINOIS

COUNTY OF LAKE

} SS

I, _____, County Clerk of Lake County, Illinois, do hereby certify that there are **no delinquent general taxes, unpaid current general taxes, delinquent special assessments or unpaid current special assessments** against any of the land included in the described property. I further certify that I have received all statutory fees in connection with the plat.

Given under my hand and seal of the County Clerk of Lake County, Illinois.

Dated this _____ day of _____, A.D. _____

Lake County Clerk

Vacation Plat

Illinois Compiled Statutes Ch. 765 Act 205/6

Any plat may be vacated by the owner of the premises at any time before the sale of any lot therein, by a written instrument to which a copy of the plat is attached, declaring it to be vacated. If there are public service facilities in the highways, streets, alleys and other public ways and in easements shown on the plat, the instrument shall reserve to the public body or public utility owning such facilities, the property, rights of way and easements necessary for continuing public service by means of those facilities and for the maintenance, renewal and reconstruction of same. The instrument shall be approved by the city council or village or county board in the same manner as plats of subdivisions. The instrument shall also be submitted for approval to the Highway Commissioner and to the county engineer or superintendent of highways and to the District Engineer of the Department of Transportation of the state and to the public utility or utilities involved. The instrument shall be executed, acknowledged or proved and recorded or filed in the same manner as plats or subdivisions. When lots have been sold the plat may be vacated in the manner provided in this section by all the owners of lots in the plat joining in the execution of the writing.

Vacating of Streets and Alleys

Municipal Vacations 65 ILCS 5/11-91-1

Whenever the corporate authorities of any municipality, whether incorporated by special act or under any general law, determine that the public interest will be subserved by vacating any street or alley, or part thereof, within their jurisdiction in any incorporated area, they may vacate that street or alley, or part thereof, by an ordinance. But this ordinance shall be passed by the affirmative vote of at least three-fourths of the aldermen, trustees or commissioners then holding office. This vote shall be taken by ayes and noes and entered on the records of the corporate authorities.

The ordinance may or may not include a plat as an exhibit. A plat without an ordinance may be accepted if reference is made to the ordinance.

Title Upon Vacation

Municipalities 65 ILCS 5/11-91-2

Except in cases where the deed, or other instrument, dedicating a street or alley, or part thereof, has expressly provided for a specific devolution of the title thereto upon the abandonment or vacation thereof, whenever any street or alley, or any part thereof, is vacated under or by virtue of any ordinance of any municipality, the title to the land included within the street or alley, or part thereof, so vacated, vests in the then owners of the land abutting thereon.

Township Roads 605 ILCS
5/6-303

Existing township and district roads may be widened, altered or vacated, and new township and district roads may be laid out in the manner provided in this Division of this Code. Any number of voters not less than 5% of the legal voters, or 12 legal voters, whichever is less, residing in any road district may file a petition with the highway commissioner of such district, praying for the laying out, widening, altering or vacation of such roads.

5/6-329

Upon the vacation of any township or district road or part thereof, the highway commissioner shall cause a legal description of the road or part thereof vacated to be recorded in the office of the recorder of the county. The recorder shall mark the plat previously recorded in such manner as to show the vacation and to indicate the book and page number where the description is recorded.

County Highways 605 ILCS 5/5-109

When the County Board determines that the public and economic interest is served by vacating a county highway or part of it, it may vacate that highway or part of it by resolution adopted by the favorable vote of 2/3 of the members of the County Board, subject to the approval of the Department (of Transportation)... The resolution may provide that it is not effective until the owners of property abutting on the highway or part of it to be vacated pay compensation in an amount which, in the judgment of the County Board, is not in excess of the fair market value of a similar acreage abutting the highway.

Vacation of Utility Easement

All you need is the utility company representative's signature. No owner signature is required.

Recording Requirements for Vacations
(excluding vacation of easement)

1. Plat must measure at least 8½" x 14", but no larger than 30" x 36".
2. The plat must contain a legal description and signature certificate from the Registered Land Surveyor as preparer including an original signature and surveyor's seal.
3. Metes and bounds descriptions must contain section, township and range with an identifiable point of beginning.
4. The plat must contain a signature certificate with original signatures of the landowner or representative of the owner.
5. The name and address of the owner must be printed under the signature.
6. The signature of the owner must be acknowledged by a Notary Public and a legible seal for the notary stamped on the plat.
7. Corporate approval (when applicable) must be indicated by the signature of the mayor/president/county chair and attested to by the municipal/county clerk including date of approval.
8. Village seal must be applied/embossed.
9. The vacation plat must be approved by the Highway Commissioner (township), county engineer or superintendent of highways, and/or the District Engineer of the Illinois Department of Transportation and the public utilities involved.
10. The County Clerk must certify that there are no delinquent or current property taxes due, or outstanding special assessments. The certificate must be signed and sealed by the County Clerk or an authorized staff member.
11. The Recorder's file stamp will indicate the date and time of recording and assign a document number.
12. Mail-to name and address required.

Annexation/Disconnection Plat

Illinois Compiled Statutes Ch. 765 Act 205/1.02

When any city, village, municipal corporation or political subdivision annexes or disconnects territory, a plat of the land included in the disconnection or annexation must be filed with the recorder in the county or counties where the territory is located. Each plat shall state a legal description or descriptions sufficient to identify the boundaries of the annexed or disconnected territory, by reference to government surveys or by metes and bounds, including the section, township and range in which the territory is located. Such a plat must be prepared by a Registered Land Surveyor or a duly employed municipal engineer registered under the laws of the State of Illinois, provided such engineer has had training in the field of civil engineering.

Municipal Annexations **65 ILCS 5/7-1-40**

A certified copy of the ordinance together with an accurate map of the annexed territory must be filed with the office of the recorder of the county in which the annexed property is located and also with the office of the recorder of the county in which the annexing municipality is located. This must be done within 90 days after the final step in the annexation process is completed. The plat of annexation must be prepared by a registered land surveyor or a duly employed municipal engineer registered under the laws of Illinois, provided such engineer has had training in the field of civil engineering.

65 ILCS 5/7-1-8

A copy of the ordinance annexing the territory together with an accurate map of the annexed territory shall be recorded with the recorder and filed with the County Clerk within the county wherever the annexed territory is located.

Park District Annexations **70 ILCS 1205/3.1**

A certified copy of the annexing ordinance shall be filed in the offices of the county clerk and recorder of each county in which the annexation takes place.

Library District Annexations **75 ILCS 16/15-80**

A copy of each annexation ordinance of any library district annexing territory, together with an accurate map of the territory annexed, shall be deposited with and recorded by the recorder and filed with the county clerk of the county in which the annexed territory is situated.

Recording sequence

Annexation ordinance and annexation agreement can be recorded in any order, but if you have an annexation and a zoning ordinance – record the annexation first.

Recording Requirements for Annexations/Disconnections

1. A certified copy of the ordinance, court order or resolution of annexation or disconnection together with an accurate map of the territory annexed or disconnected must be recorded with the County Recorder and County Clerk. (Plat size must be between 8½" x 14" and 30" x 36".)
2. The certified copy must include an original signature and the village seal must be applied/embossed.
3. The map must contain a legal description and signature certificate from the Registered Land Surveyor of municipal engineer as preparer including signature and surveyor's seal.
4. Metes and bounds descriptions must contain section, township and range with an identifiable point of beginning.
5. The Recorder's file stamp will indicate the date and time of recording and assign a document number.
6. Mail-to name and address required.

Plat Certificate of Amendment / Plat Certificate of Correction

1. The certificate must contain a description of the amendment or correction, referencing the plat name, document number and recorded date prepared by the surveyor.
2. The surveyor must sign and seal the certificate.
3. **The certificate of correction need only be signed by the surveyor. A certificate of amendment must contain a signature certificate with original signatures of the landowner or a representative of the owner. It must also contain an original signature and the embossed (or otherwise applied) seal of the Village or County, whomever approved the original plat.**
4. If the property is owned under a Trust, the Trust Officer signature and seal of the bank (if available) must be included on the certificate of amendment.
5. The name and address of the owner(s) or Trust Officer are to be printed under each signature.
6. The signature of the owner(s) must be acknowledged by a Notary Public and a legible seal for the notary stamped on the plat.
7. The certificate of amendment or correction will be recorded and filed with the original plat of subdivision.
8. Mail-to name and address required.

(Rev. 9/14/98)

Samples and Exhibits

- (a) Samples of Surveyor's Certificates
- (b) Sample School District Certificate
- (c) Sample County Highway Signature Certificates
- (d) Plat Act Affidavit
- (e) Request for Consolidation or Division of Tax Parcels
- (f) Schedule of Fees

Samples of Surveyor's Certificates

(Re: Special Powers authorized by Division 12 of Article 11 of the Illinois Municipal Code and Flood Hazard Areas)

1.) **LOCATED WITHIN CORPORATE LIMITS (REQUIRES MUNICIPAL APPROVAL)**

"I further certify that the attached plat is a true and correct representation of said survey and subdivision. All distances shown in feet and decimals parts thereof, that the property hereon shown and described is within the corporate limits of the (CITY/VILLAGE) of _____ Lake County, Illinois, and that said property is designated as "Zone – C" defined as areas of minimal flooding as shown in the flood insurance rate map Community Panel No. _____, dated _____ as published by the Federal Emergency Management Agency."

2.) **LOCATED OUTSIDE CORPORATE LIMITS BUT WITHIN 1.5 MILE LIMIT OF MUNICIPALITY WHICH HAS ADOPTED A COMPREHENSIVE PLAN AND IS EXERCISING ITS POWERS (REQUIRES MUNICIPAL AND COUNTY APPROVAL)**

"I further certify that the attached plat is a true and correct representation of said survey and subdivision. All distances shown in feet and decimals parts thereof. Part of the above described tract is located within the area designated as flood hazard as shown in the flood insurance rate map Community Panel No. _____, dated _____ as published by the Federal Emergency Management Agency. Said tract is not within the corporate limits, but is within 1.5 miles of the corporate limits of the (CITY/VILLAGE) of _____ Lake County, Illinois, which has adopted and is exercising the special powers authorized by Division 12 of Article 11 of the Illinois Municipal Code."

3.) **LOCATED OUTSIDE CORPORATE LIMITS BUT WITHIN 1.5 MILE LIMIT OF MUNICIPALITY WHICH HAS ADOPTED A COMPREHENSIVE PLAN BUT IS NOT EXERCISING ITS POWERS (REQUIRES COUNTY APPROVAL)**

"I further certify that the attached plat is a true and correct representation of said survey and subdivision. All distances shown in feet and decimals parts thereof. The above described tract is not located within the area designated as flood hazard as identified by the Federal Emergency Management Agency. Said tract is within 1.5 miles of the corporate limits of the (CITY/VILLAGE) of _____ Lake County, Illinois, which has adopted the special powers authorized by Division 12 of Article 11 of the Illinois Municipal Code, but is not exercising said powers."

4.) **LOCATED OUTSIDE CORPORATE LIMITS AND OUTSIDE 1.5 MILE LIMIT OF MUNICIPALITY WHICH HAS ADOPTED A COMPREHENSIVE PLAN (REQUIRES COUNTY APPROVAL)**

"I further certify that the attached plat is a true and correct representation of said survey and subdivision. All distances shown in feet and decimals parts thereof. Part of the above described property is located within the area designated as flood hazard as shown in the flood insurance rate map Community Panel No. _____, dated _____ as published by the Federal Emergency Management Agency. Said property is not located within 1.5 miles of the corporate limits of any city or village in Lake County, Illinois, which has adopted a comprehensive plan."

Sample School District Certificate

This is to certify that I _____ as owner of the property described as the _____ Subdivision and legally described on the plat of the same name, have determined to the best of my knowledge the school district in which each of the following lots lies.

Signature of Owner

SCHOOL DISTRICTS
ELEMENTARY HIGH SCHOOL

LOT NUMBER(S)

STATE OF ILLINOIS

COUNTY OF LAKE

} SS

I, _____, a Notary Public, do hereby certify that _____
_____, owner of the property commonly known as _____

Subdivision, appeared before me this day in person and acknowledged the execution of this statement as his free and voluntary act.

Given under my hand and notarial seal this _____ day of _____, _____.

seal

Notary Public

(Rev. 5/20/98)

Sample County Highway Signature Certificates

Access prohibited

STATE OF ILLINOIS

COUNTY OF LAKE



SS

This plat is hereby approved this _____ day of _____, _____ by
the County Engineer of Lake County pursuant to Chapter 765, Act 205, Section 2 of the Illinois Compiled
Statutes, as amended, as to roadway access to County Highway __, also known as _____
_____.

Direct access either to or from County Highway _____ is prohibited as shown on this plat.

County Engineer

Access allowed, but restricted

STATE OF ILLINOIS

COUNTY OF LAKE



SS

This plat is hereby approved this _____ day of _____, _____ by
the County Engineer of Lake County pursuant to Chapter 765, Act 205, Section 2 of the Illinois Compiled
Statutes, as amended, as to roadway access to County Highway __, also known as _____
_____.

Direct access either to or from County Highway _____ shall be restricted as shown on this plat
and shall be subject to the Lake County Highway access regulation ordinance which requires, in part,
that application be made and an access permit be obtained from the County Engineer of Lake County
prior to any access installation.

County Engineer



Plat Act Affidavit

18 N County St – 6th Floor
Waukegan, IL 60085-4358
Phone: (847) 377-2575
FAX: (847) 984-5860

STATE OF ILLINOIS

COUNTY OF LAKE

} SS

I, (name) _____, being duly sworn on oath, state that I reside at _____, and that the attached deed is not in violation of the Plat Act, Ch. 765 ILCS 205/1.1(b), as the provisions of this Act do not apply and no plat is required due to the following allowed exception **(Circle the number applicable to the attached deed):**

1. The division or subdivision of land into parcels or tracts of 5 acres or more in size which does not involve any new streets or easements of access;
2. The division of lots or blocks of less than 1 acre in any recorded subdivision which does not involve any new streets or easements of access;
3. The sale or exchange of parcels of land between owners of adjoining and contiguous land;
4. The conveyance of parcels of land or interests therein for use as a right of way for railroads or other public utility facilities and other pipe lines which does not involve any new streets or easements of access;
5. The conveyance of land owned by a railroad or other public utility which does not involve any new streets or easements of access;
6. The conveyance of land for highway or other public purposes or grants or conveyances relating to the dedication of land for public use or instruments relating to the vacation of land impressed with a public use;
7. Conveyances made to correct descriptions in prior conveyances;
8. The sale or exchange of parcels or tracts of land following the division into no more than 2 parts of a particular parcel or tract of land existing on July 17, 1959, and not involving any new streets or easements of access;
9. The sale of a single lot of less than 5 acres from a larger tract when a survey is made by an Illinois Registered Land Surveyor; provided, that this exemption shall not apply to the sale of any subsequent lots from the same larger tract of land, as determined by the dimensions and configuration of the larger tract on October 1, 1973, and provided also that this exemption does not invalidate any local requirements applicable to the subdivision of land;
10. The conveyance of land does not involve any land division and is described in the same manner as title was taken by grantor(s).

AFFIANT further states that this affidavit is made for the purpose of inducing the RECORDER OF LAKE COUNTY, ILLINOIS to accept the attached deed for recording. (This affidavit is not applicable to Facsimile Assignment of Beneficial Interest.)

SUBSCRIBED and SWORN to before me this ____ day
of _____, _____

(Signature)

Notary: _____
(seal)



**Chief County Assessment Office
Mapping Division**
18 N County St – 7th Floor
Waukegan, IL 60085
Phone: (847) 377-2373
Email: maps@lakecountyil.gov

Request for Consolidation or Division of Tax Parcels

Date: _____

- ☐ Request for a **consolidation** of the following Permanent Index Numbers (PIN)

- ☐ Request for a **division** of property for tax purposes.

The following Permanent Index Number (PIN) involved as underlying land for this division is:

The legal description of the part being divided out is:

Note: If necessary, use the reverse side for a continuation of the legal description or attach on a separate sheet. A plat of survey with a legal is acceptable. If more than one new tax parcel is being created from the same underlying land, attach information regarding the legal description, taxpayer and property location on a separate sheet for each additional parcel.

NEW TAX PARCEL INFORMATION

TAXPAYER Name: _____

TAXPAYER Address: _____

PROPERTY LOCATION (if available)

Address: _____

SIGNATURE REQUIRED TO PROCESS REQUEST

Owner or Authorized party: _____

Address: _____

Phone: _____

Note: Consolidations or divisions will be done for the tax year following the date of the request of the date the request is received by this office. This request is subject to a check for all unpaid and delinquent taxes on any parcels that are listed (please see certificate on next page). The request will not be acted on until all unpaid taxes are paid and/or redeemed.

COUNTY CLERK'S CERTIFICATE

NOTE: An original certificate must be submitted for each property.

STATE OF ILLINOIS }
COUNTY OF LAKE } SS

The Lake County Clerk's Office hereby certifies that there are no delinquent general taxes, unpaid current general taxes, delinquent special assessments or unpaid current special assessments against any of the land included in the described property on the above Request for Consolidation or Division of Tax Parcels Form.

Given under my hand and seal of the County Clerk of Lake County, Illinois.

This _____ day of _____, _____.

Lake County Clerk or Deputy County Clerk

Important Information About Dividing Property For Tax Purposes

As a result of creating a land division for tax purposes, you MAY create parcels which MIGHT not meet requirements for the improvement of land (building permits.)

If you wish to divide a parcel in Lake County, please read the following information carefully, in order to protect yourself or your client.

A parcel owner may wish to divide the parcel into two or more new parcels, for tax purposes. This procedure is available through the Mapping Division of the Chief County Assessment Office. However, if the owner wished to sell one of the resulting parcels at some later date to another party, the parcel in question may not necessarily meet all local development permitting requirements, if the new owner intended to improve the parcel.

Therefore, simply creating a tax parcel through the Mapping Division **does not guarantee** that the parcel may be built upon or improved, due to local permitting requirements. The resulting burden on the landowner might be avoided through simple administrative review by all applicable permitting agencies or departments prior to the creation of a tax parcel.

If your property is in unincorporated Lake County, you can call the Lake County Planning, Building and Development Department at (847) 377-2600 for such a review at no charge.

Please note that the informal County administrative review suggested herein is performed as a courtesy only and is not intended and should not be interpreted to create or cause the vesting of any property rights. Nor does the suggested County review relieve a landowner from complying with all applicable local development regulations and obtaining all required permits and approvals prior to development or improvement of land.

If your property is within a city or village, you can contact the municipal department responsible for building permits to discuss their local requirements.

Schedule of Fees

RECORDING FEES

SUBDIVISION PLATS

First page	\$77.00
Additional pages	\$1.00 each

CONDOMINIUM DECLARATION / AMENDMENT / SUPPLEMENT

First page	\$39.00
Additional pages	\$1.00 each
Condominium plat exhibit – first page	\$50.00
Additional condominium plat exhibit pages	\$1.00 each

PLATS OF SURVEY (No more than 2 lots or parcels)

As a separate document	\$39.00
As exhibit	\$12.00
Additional pages	\$1.00 each

MISCELLANEOUS PLATS (Easements, Vacations, Dedication, Annexation, Plans)

As a separate document	\$39.00
As exhibit	\$12.00
Additional pages	\$1.00 each

COPIES FEES

PLATS

Paper copy (reduced, enlarged or full size)	\$5.00 per page
Digital image via email (TIF / PDF format)	\$5.00 per image (page)
Digital image on CD or via FTP (TIF / PDF format) on a daily, weekly or monthly basis	\$10.00 CD/FTP processing fee plus \$5.00 per image (page)
Certified Plat Copies (55 ILCS 5/3-5018)	\$10.00


LAKE COUNTY
DIVISION OF TRANSPORTATION
RIGHT OF WAY PLANS
FOR PROPOSED
FEDERAL AID HIGHWAY

ROUTE: OLD McHENRY ROAD (COUNTY HIGHWAY #32)
SECTION: 11-00083-09-RS
PROJECT NO.:
JOB NO.:
COUNTY: LAKE
LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD

* OLD McHENRY ROAD (COUNTY HIGHWAY #32)

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	LAKE	16	1
F.H.W.A. REG.	ILLINOIS	PROJECT		

** 11-00083-09-RS





LOCATION OF SECTION INDICATED THUS: [Symbol]

PARCEL NUMBER	OWNER	SHEET NUMBER	PROPERTY ACQUIRED BY
0001T.E.	Village of Long Grove	2 & 11	
0002 0002T.E.	Village of Long Grove	2 & 11	
0003-A 0003-B 0003T.E.	Long Grove Investments, LLC, an Illinois limited liability company	3, 6 & 12	
0004T.E.	Lawrence Gutkin and Maggie Gutkin, husband and wife as joint tenants	2	
0005T.E.	Spirit Lake Acquisition I LLC, a Delaware limited liability company	4	
0006T.E.-A 0006T.E.-B	PGF, LLC, a Colorado Limited Liability Company	5 & 13	
0007T.E.	Long Green, Inc., a dissolved Illinois corporation	5	
0008	Karen Gritis and Micheal DeMar, as joint tenants	6	
0009 0009T.E.	Long Green, Inc., a dissolved Illinois corporation	7	
0010T.E.	Dolores Towner, as Trustee of the Dolores Towner Revocable Living Trust dated October 9, 1997	8	
0011T.E.	The Village Tavern of Long Grove, Inc. a corporation of the State of Illinois	7	
0012T.E.	Gene Albert	9	
0013T.E.	The Board of Education of Kildeer-Countryside Community Consolidated School District #96, a Body Politic	10 & 14	
0014T.E.-A 0014T.E.-B	Marsha Forsythe-Fournier	10 & 14	

RANGE 10 EAST | RANGE 11 EAST

TOWNSHIP 43 NORTH



PROJECT LENGTH = 2,554.09 LIN. FT. = 0.484 MILE, OLD McHENRY ROAD
= 61.00 LIN. FT. = 0.011 MILE, ARCHER ROAD
= 373.85 LIN. FT. = 0.071 MILE, ROBERT PARKER COFFIN ROAD - WEST
= 114.01 LIN. FT. = 0.022 MILE, ROBERT PARKER COFFIN ROAD - EAST
TOTAL LENGTH = 3,102.95 LIN. FT. = 0.588 MILES

APPROVED _____ 20 _____

LOCAL AGENCY OFFICIAL

APPROVED _____ 20 _____

ENGINEER OF LAND ACQUISITION

APPROVED _____ 20 _____

ENGINEER OF LOCAL ROADS & STREETS

APPROVED _____ 20 _____

DISTRICT ENGINEER

LAKE COUNTY
DIVISION OF TRANSPORTATION

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.

STATE OF ILLINOIS }
COUNTY OF LAKE }SS

I, PAULA J. TRIGG, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY
CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF
THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY 32 IN
SAID COUNTY.

DATED THIS _____ DAY OF _____ 20____ A.D.

COUNTY ENGINEER

Ensure that the County
Engineer statement &
signature block is on each
plat page.

Existing & Proposed
Pavement
Archer Road
Curve #1

P.I. = Sta. 100+80.55
Δ = 27°28'20"
R = 100.00'
L = 24.44'
E = 47.95'
F = 2.94'
P.C. = Sta. 100+56.11
P.T. = Sta. 101+04.06

See Sheet 11
for Total Holdings
Parcel 0002
& 0002T.E.

See Sheet 3 for
Parcel 0003-A &
0003T.E.

See
Detail
"A"

Proposed Temporary
Easement Line

See Sheet 4 for
Parcel 0005T.E.

RED OAKS
Recorded December 26, 1986
as Document No. 2519282
Corrected by Certificates of Correction
Recorded July 16, 1987
as Document No. 2590825
and Recorded July 27, 1987
as Document No. 2594571

ARCHER LOTS
SUBDIVISION
Recorded December 12, 2011
as Document No. 6798242

Detail "A"
Scale: 1"=5'

PROJECT COORDINATES Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
15+60.98	40.00' Rt.	2,007,518.934	1,075,616.497
16+03.15	40.00' Lt.	2,007,470.367	1,075,540.214
16+60.00	40.00' Lt.	2,007,498.551	1,075,490.841
16+60.00	42.00' Lt.	2,007,496.814	1,075,489.850
16+80.99	40.00' Lt.	2,007,508.959	1,075,472.609
16+81.35	42.00' Lt.	2,007,507.398	1,075,471.310
100+50.00	33.00' Lt.	2,007,527.613	1,075,621.464
100+50.00	38.21' Lt.	2,007,530.196	1,075,616.939
100+55.00	40.81' Lt.	2,007,535.828	1,075,617.160
100+56.11	33.00' Lt.	2,007,532.925	1,075,624.496
100+56.11	33.00' Rt.	2,007,500.206	1,075,681.812
100+58.35	33.00' Lt.	2,007,534.232	1,075,625.223
100+61.00	33.00' Lt.	2,007,535.806	1,075,626.049
100+61.00	33.00' Rt.	2,007,505.926	1,075,684.895
101+04.06	33.00' Lt.	2,007,563.512	1,075,633.258
101+04.06	33.00' Rt.	2,007,560.924	1,075,699.204

SURVEY AND DIVISION
Recorded November 25, 1930
as Document No. 362197
Corrected by Certificate of Correction
Recorded February 26, 1931
as Document No. 365601

PARCEL NUMBER	TOTAL HOLDINGS ACRES	PART TAKEN		AREA IN EXISTING R.O.W. ACRES	REMAINDER AREA ACRES	EASEMENT AREA		EASEMENT PURPOSE	PERMANENT INDEX NUMBER
		ACRES	SQUARE FEET			ACRES	SQUARE FEET		
0001T.E.	3.806	N/A	N/A	N/A	3.806	0.001	62	Grading	15-30-108-007 15-30-108-008 15-30-108-009 15-30-108-010 15-30-108-011
0002 0002T.E.	0.127	0.000	20	N/A	0.127	0.001	30	Grading	15-30-110-001
0004T.E.	0.159	N/A	N/A	N/A	0.159	0.001	42	Driveway Construction	15-30-106-018

REVISION DATE

REVISION


MADE BY

EXISTING R.O.W. RECORDED INFORMATION		
Parcel	Document No.	Date Recorded
0001	6529810	October 7, 2009
0001	6798242	December 12, 2011
0002	6529810	October 7, 2009
0002	6798242	December 12, 2011
0004	521616	November 27, 1942
----	521238	November 17, 1942
----	521239	November 17, 1942
----	521242	November 17, 1942
----	521442	November 23, 1942
----	521447	November 23, 1942
----	521617	November 27, 1942
----	521618	November 27, 1942

LEGEND




SECTION
CORNER



QUARTER
SECTION
CORNER

SECTION LINE
QUARTER SECTION LINE
QUARTER SECTION LINE
PLATTED LOT LINE
PROPERTY (DEED) LINE

APL
APPARENT PROPERTY LINE
EXISTING CENTER LINE
PROPOSED CENTER LINE
EXISTING RIGHT OF WAY LINE
PROPOSED RIGHT OF WAY LINE
EXISTING EASEMENT
PROPOSED EASEMENT
EXISTING ACCESS CONTROL LINE
PROPOSED ACCESS CONTROL LINE
MEASURED DIMENSION
COMPUTED DIMENSION
RECORD DIMENSION



EXISTING BUILDING

Bearings and Coordinates are referenced to the
Illinois Coordinate System NAD 83(2011) East Zone.

○ IRON PIPE OR ROD FOUND
+ CUT CROSS FOUND OR SET
● "MAG" NAIL SET
● 5/8" REBAR SET

● T1
● T2
● T3
● BT1
● BT2
● BT3
● THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH
IRON ROD FLUSH WITH GROUND TO THE FOUND IRON STAKE. IDENTIFIED BY
COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.

● BT1
● BT2
● BT3
● THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONU-
MENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO THE
FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SUR-
VEYORS REGISTRATION NUMBER.

■ STAKING OF PROPOSED RIGHT OF WAY. SET DIVISION OF HIGHWAYS SURVEY
MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION
DATA AND SURVEYORS REGISTRATION NUMBER.

■ M STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS. BURIED 5/8
INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY
MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING
SURVEYORS REGISTRATION NUMBER.

● PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)

□ RIGHT OF WAY STAKING PROPOSED TO BE SET.

STATE OF ILLINOIS }
COUNTY OF LAKE }SS

THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS
PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE
SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N.,
RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS
TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT
THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND
ESTABLISHED ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON
AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED.
MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.

DATED AT LAKE VILLA, ILLINOIS THIS _____ DAY OF _____ 20____ A.D.

PRESIDENT
ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016

THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT
ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.

All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.
All measured and computed distances are grid not ground.
To obtain ground distances, divide grid distances shown by
the combined factor of 0.9999548166.

PROJECT COORDINATES Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
13+94.36	50.00' Rt.	2,007,445.018	1,075,766.153
13+99.98	40.00' Rt.	2,007,439.120	1,075,756.315
14+85.00	50.00' Rt.	2,007,489.952	1,075,687.438
14+94.97	50.00' Rt.	2,007,494.895	1,075,678.780

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371


PLAT OF HIGHWAYS
LAKE COUNTY
DIVISION OF TRANSPORTATION
OLD McHENRY ROAD (COUNTY HIGHWAY #32)

LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION 13+00 TO STATION 18+00
STATION 100+00.00 TO STATION 102+00
SCALE: 1"=20' SHEET 2 OF 16

LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.

PARCEL NUMBER	TOTAL HOLDINGS ACRES	PART TAKEN ACRES	AREA IN EXISTING R.O.W. ACRES	REMAINDER AREA ACRES	EASEMENT AREA ACRES	EASEMENT PURPOSE	PERMANENT INDEX NUMBER
0003-A 0003-B 0003T.E.	3.020	A=0.022 B=0.064	A=0.021 B=0.062	2.934	0.047	Construction Purposes	15-30-100-015 15-30-100-018 15-30-100-019 15-30-104-001 15-30-104-002



PROJECT COORDINATES Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
15+73.00	0	2,007,490.158	1,075,586.227
15+73.00	40.00' Rt.	2,007,524.894	1,075,606.056
15+96.58	45.00' Rt.	2,007,540.926	1,075,588.057
15+96.58	55.00' Rt.	2,007,549.611	1,075,593.014
17+95.29	0	2,007,600.360	1,075,393.174
18+17.03	40.00' Rt.	2,007,645.871	1,075,394.129
18+55.00	45.00' Rt.	2,007,669.040	1,075,363.629
18+55.00	50.00' Rt.	2,007,673.382	1,075,366.108
18+90.00	40.00' Rt.	2,007,682.049	1,075,330.754
18+90.00	50.00' Rt.	2,007,690.733	1,075,335.711
100+50.00	33.00' Lt.	2,007,527.613	1,075,621.464
100+56.11	33.00' Lt.	2,007,532.925	1,075,624.496
100+56.11	33.00' Lt.	2,007,500.206	1,075,681.812
101+04.06	33.00' Lt.	2,007,563.512	1,075,633.258
101+04.06	33.00' Rt.	2,007,560.924	1,075,699.204

Detail "B"
Scale: 1"=20'

STATE OF ILLINOIS }
COUNTY OF LAKE }
I, PAULA J. TRIGG, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY 32 IN SAID COUNTY.
DATED THIS ____ DAY OF ____ 20__ A.D.

COUNTY ENGINEER

EXISTING R.O.W. RECORDED INFORMATION		
Parcel	Document No.	Date Recorded
0003	521242	November 17, 1942
0003	521442	November 23, 1942
0003	521443	November 23, 1942
0003	521617	November 27, 1942
----	521239	November 17, 1942
----	521242	November 17, 1942
----	521447	November 23, 1942
----	521616	November 27, 1942
----	521618	November 27, 1942
----	524356	February 18, 1943
----	6529810	October 7, 2009
----	6798242	December 12, 2011

Schedule of Ties		
Point Number	Tie to point	Tie Distance (feet)
1	T1 T2 T3	

SURVEY AND DIVISION
Recorded November 25, 1930
as Document No. 362197
Corrected by Certificate of Correction
Recorded February 26, 1931
as Document No. 365601

REVISION DATE

REVISION

SECTION CORNER

16

15

QUARTER SECTION CORNER

SECTION LINE

QUARTER SECTION LINE

QUARTER, QUARTER SECTION LINE

PLATTED LOT LINE

PROPERTY (DEED) LINE

APL

APPARENT PROPERTY LINE

EXISTING CENTER LINE

PROPOSED CENTER LINE

EXISTING RIGHT OF WAY LINE

PROPOSED RIGHT OF WAY LINE

EXISTING EASEMENT

PROPOSED EASEMENT

EXISTING ACCESS CONTROL LINE

PROPOSED ACCESS CONTROL LINE

MEASURED DIMENSION

COMPUTED DIMENSION

RECORD DIMENSION

EXISTING BUILDING

0

20'

40'

SCALE: 1"=20'

Bearings and Coordinates are referenced to the Illinois Coordinate System NAD 83(2011) East Zone.

IRON PIPE OR ROD FOUND

CUT CROSS FOUND OR SET

T1

T2

T3

BT1

BT2

BT3

"MAG" NAIL SET

5/8" REBAR SET

THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH IRON ROD FLUSH WITH GROUND TO THE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.

THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONUMENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO THE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.

STAKING OF PROPOSED RIGHT OF WAY. SET DIVISION OF HIGHWAYS SURVEY MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION DATA AND SURVEYORS REGISTRATION NUMBER.

STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS. BURIED 5/8 INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.

PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)

RIGHT OF WAY STAKING PROPOSED TO BE SET.

THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS PROFESSIONAL DESIGN FIRM/LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N., RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND ESTABLISHED ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED. MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.
DATED AT LAKE VILLA, ILLINOIS THIS ____ DAY OF ____ 20__ A.D.

PRESIDENT
ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016
THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.
All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.
All measured and computed distances are grid not ground.
To obtain ground distances, divide grid distances shown by the combined factor of 0.9999548166.

PROJECT COORDINATES Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
14+94.97	50.00' Rt.	2,007,494.895	1,075,678.780
15+40.18	0	2,007,473.887	1,075,614.729
15+60.98	40.00' Rt.	2,007,518.934	1,075,616.497
15+66.18	50.00' Rt.	2,007,530.196	1,075,616.939
15+68.78	55.00' Rt.	2,007,535.828	1,075,617.160

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371

PLAT OF HIGHWAYS
LAKE COUNTY
DIVISION OF TRANSPORTATION
OLD McHENRY ROAD (COUNTY HIGHWAY #32)
LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION 14+00 TO STATION 20+00
STATION 100+00.00 TO STATION 102+00
SCALE: 1"=20' SHEET 3 OF 16

LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.

STATE OF ILLINOIS }
COUNTY OF LAKE }
I, PAULA J. TRIGG, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY 32 IN SAID COUNTY.
DATED THIS _____ DAY OF _____, 20____ A.D.

COUNTY ENGINEER

LEGEND

SECTION CORNER
QUARTER SECTION CORNER

SECTION LINE
QUARTER SECTION LINE
QUARTER SECTION LINE
PLATTED LOT LINE
PROPERTY (DEED) LINE

APL
APPARENT PROPERTY LINE
EXISTING CENTER LINE
PROPOSED CENTER LINE
EXISTING RIGHT OF WAY LINE
PROPOSED RIGHT OF WAY LINE
EXISTING EASEMENT
PROPOSED EASEMENT
EXISTING ACCESS CONTROL LINE
PROPOSED ACCESS CONTROL LINE
MEASURED DIMENSION
COMPUTED DIMENSION
RECORD DIMENSION

EXISTING BUILDING

SCALE: 1"=20'

Bearings and Coordinates are referenced to the Illinois Coordinate System NAD 83(2011) East Zone.

- IRON PIPE OR ROD FOUND
CUT CROSS FOUND OR SET
- "MAG" NAIL SET
5/8" REBAR SET
- THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH IRON ROD FLUSH WITH GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONUMENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- STAKING OF PROPOSED RIGHT OF WAY. SET DIVISION OF HIGHWAYS SURVEY MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION DATA AND SURVEYORS REGISTRATION NUMBER.
- STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS. BURIED 5/8 INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)
- RIGHT OF WAY STAKING PROPOSED TO BE SET.

STATE OF ILLINOIS }
COUNTY OF LAKE }
THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N., RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND ESTABLISHED ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED. MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.
DATED AT LAKE VILLA, ILLINOIS THIS _____ DAY OF _____, 20____ A.D.

PRESIDENT
ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016
THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.

All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.
All measured and computed distances are grid not ground.
To obtain ground distances, divide grid distances shown by the combined factor of 0.9999548166.

PROJECT COORDINATES Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
16+80.99	40.00' Lt.	2,007,508.959	1,075,472.609
17+80.00	40.00' Lt.	2,007,558.042	1,075,386.626
17+80.00	42.00' Lt.	2,007,556.305	1,075,385.634
18+21.75	40.00' Lt.	2,007,578.741	1,075,350.365

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371

PLAT OF HIGHWAYS
LAKE COUNTY
DIVISION OF TRANSPORTATION
OLD McHENRY ROAD (COUNTY HIGHWAY #32)
LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION 16+00 TO STATION 19+00
SCALE: 1"=20' SHEET 4 OF 16
LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

EXISTING R.O.W. RECORDED INFORMATION		
Parcel	Document No.	Date Recorded
0005	521239	November 17, 1942
----	521239	November 17, 1942
----	521242	November 17, 1942
----	521442	November 23, 1942
----	521616	November 27, 1942
----	524356	February 18, 1943

PARCEL NUMBER	TOTAL HOLDINGS ACRES	PART TAKEN ACRES	AREA IN EXISTING R.O.W. ACRES	REMAINDER AREA ACRES	EASEMENT AREA ACRES	EASEMENT SQUARE FEET	EASEMENT PURPOSE	PERMANENT INDEX NUMBER
0005T.E.	1.469	N/A	N/A	1.469	0.002	84	Driveway Construction	15-30-106-015 15-30-106-016 15-30-106-017

SURVEY AND DIVISION
Recorded November 25, 1930
as Document No. 362197
Corrected by Certificate of Correction
Recorded February 26, 1931
as Document No. 365601

SEE SHEET 2

REVISION DATE

REVISION

MADE BY

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.

STATE OF ILLINOIS }
COUNTY OF LAKE }SS

I, PAULA J. TRIGG, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY 32 IN SAID COUNTY.

DATED THIS _____ DAY OF _____, 20____ A.D.

COUNTY ENGINEER

EXISTING R.O.W. RECORDED INFORMATION		
Parcel	Document No.	Date Recorded
0006	521242	November 17, 1942
0006	524356	February 18, 1943
0007	250627	December 29, 1924
0007	521444	November 23, 1942
----	521239	November 17, 1942
----	521242	November 17, 1942
----	521443	November 23, 1942
----	521446	November 23, 1942
----	602679	October 14, 1946
----	991876	June 3, 1958

PROJECT COORDINATES Illinois Coordinate System NAD 83(2011) East Zone				
STATION	OFFSET	NORTH	EAST	
19+25.00	40.00' Lt.	2,007,629.926	1,075,260.699	
19+25.00	45.00' Lt.	2,007,625.584	1,075,258.220	
19+86.75	40.00' Lt.	2,007,660.540	1,075,207.071	
19+87.00	42.00' Lt.	2,007,658.926	1,075,205.863	
19+95.35	℄	2,007,699.540	1,075,219.431	
20+00.00	42.00' Lt.	2,007,665.371	1,075,194.573	
20+00.00	45.00' Lt.	2,007,662.766	1,075,193.086	
20+02.88	40.00' Lt.	2,007,668.536	1,075,193.063	
20+03.82	45.00' Lt.	2,007,664.660	1,075,189.766	
20+22.00	42.00' Lt.	2,007,676.278	1,075,175.467	
20+22.00	45.00' Lt.	2,007,673.672	1,075,173.979	
20+42.00	40.00' Lt.	2,007,687.930	1,075,159.089	
20+42.00	42.00' Lt.	2,007,686.193	1,075,158.097	
20+48.80	40.00' Rt.	2,007,760.775	1,075,192.842	
20+71.52	40.00' Rt.	2,007,772.118	1,075,172.787	
21+07.68	39.40' Lt.	2,007,720.085	1,075,102.759	
21+25.26	1.02' Rt.	2,007,763.952	1,075,106.595	
21+35.82	40.00' Rt.	2,007,803.346	1,075,115.563	
21+82.26	40.00' Lt.	2,007,753.858	1,075,037.414	
203+49.23	27.50' Rt.	2,007,651.771	1,075,010.321	
203+50.39	5.49' Lt.	2,007,678.282	1,074,990.671	


Existing & Proposed Old McHenry Road Curve #1		Existing & Proposed Robert Parker Coffin Road Curve #2	
P.I. = Sta. 22+15.27	Δ = 6°39'04"	P.I. = Sta. 203+89.10	Δ = 7°04'10"
R = 2864.77'	T = 166.47'	R = 954.93'	T = 58.99'
L = 332.56'	E = 4.83'	L = 117.82'	E = 1.82'
P.C. = Sta. 20+48.80	P.T. = Sta. 23+81.36	P.C. = Sta. 203+30.11	P.T. = Sta. 204+47.93

PARCEL NUMBER	TOTAL HOLDINGS ACRES	PART TAKEN ACRES	AREA IN EXISTING R.O.W. ACRES	REMAINDER AREA ACRES	EASEMENT ACRES	AREA SQUARE FEET	EASEMENT PURPOSE	PERMANENT INDEX NUMBER
0006T.E.-A 0006T.E.-B	1.775	N/A	N/A	1.775	0.003 0.001	139 43	Driveway Construction Driveway Construction	15-30-100-034 15-30-100-035
0007T.E.	0.568	N/A	N/A	0.568	0.003	133	Driveway Construction	15-30-105-008

LEGEND




SECTION CORNER




QUARTER SECTION CORNER

SECTION LINE
QUARTER SECTION LINE
QUARTER SECTION LINE
PLATTED LOT LINE
PROPERTY (DEED) LINE

APL
EXISTING CENTER LINE
PROPOSED CENTER LINE
EXISTING RIGHT OF WAY LINE
PROPOSED RIGHT OF WAY LINE
EXISTING EASEMENT
PROPOSED EASEMENT
EXISTING ACCESS CONTROL LINE
PROPOSED ACCESS CONTROL LINE
MEASURED DIMENSION
120.32'
129.32'(Comp.)
(129.32')



EXISTING BUILDING



Bearings and Coordinates are referenced to the Illinois Coordinate System NAD 83(2011) East Zone.

○ IRON PIPE OR ROD FOUND ⊕ "MAG" NAIL SET
+ CUT CROSS FOUND OR SET ● 5/8" REBAR SET

● T1 THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH
T2 IRON ROD FLUSH WITH GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY
T3 COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.

● BT1 THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONU-
BT2 MENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO TIE
BT3 FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SUR-
VEYORS REGISTRATION NUMBER.

■ STAKING OF PROPOSED RIGHT OF WAY. SET DIVISION OF HIGHWAYS SURVEY
MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION
DATA AND SURVEYORS REGISTRATION NUMBER.

■ M STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS. BURIED 5/8
INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY
MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING
SURVEYORS REGISTRATION NUMBER.

⊙ PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)

□ RIGHT OF WAY STAKING PROPOSED TO BE SET.

STATE OF ILLINOIS }
COUNTY OF LAKE }SS

THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N., RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND ESTABLISHED ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED. MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.

DATED AT LAKE VILLA, ILLINOIS THIS _____ DAY OF _____, 20____ A.D.

PRESIDENT

ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016

THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.

All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.
All measured and computed distances are grid not ground.
To obtain ground distances, divide grid distances shown by the combined factor of 0.9999548166.

PROJECT COORDINATES Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
18+89.67	℄	2,007,647.147	1,075,311.213
18+96.75	40.00' Lt.	2,007,615.921	1,075,285.233
18+97.64	45.00' Lt.	2,007,612.018	1,075,281.985

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371

PLAT OF HIGHWAYS LAKE COUNTY DIVISION OF TRANSPORTATION

OLD McHENRY ROAD (COUNTY HIGHWAY #32)

LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION 18+00 TO STATION 23+00
STATION 203+30.11 TO STATION 204+89.76
SCALE: 1"=20' SHEET 5 OF 16

LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

REVISION DATE

REVISION


MADE BY

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.

Schedule of Ties		
Point Number	Tie to point	Tie Distance (feet)
1	T1 T2 T3	
2	T1 T2 T3	
3	T1 T2 T3	
4	T1 T2 T3	
5	T1 T2 T3	

WILLIAM UMBDENSTOCK SUBDIVISION
FIRST ADDITION
Recorded March 25, 1965
as Document No. 1257888

1



STATE OF ILLINOIS }
COUNTY OF LAKE }
I, PAULA J. TRIGG, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY 32 IN SAID COUNTY.
DATED THIS ____ DAY OF ____ 20__ A.D.

COUNTY ENGINEER						
PARCEL NUMBER	TOTAL HOLDINGS ACRES	PART TAKEN ACRES	AREA IN EXISTING R.O.W. ACRES	REMAINDER AREA ACRES	EASEMENT AREA ACRES	PERMANENT INDEX NUMBER
0003-A 0003-B 0003T.E.	3.020	A=0.022 B=0.064	A=0.021 B=0.062	2.934	0.047	15-30-100-015 15-30-100-018 15-30-100-019 15-30-104-001 15-30-104-002
0008	0.276	0.037	0.035	0.239	N/A	15-30-100-014

PROJECT COORDINATES Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
20+58.21	44.94' Rt.	2,007,769.790	1,075,186.987
21+25.26	1.02' Rt.	2,007,763.952	1,075,106.595
21+47.20	0.60' Lt.	2,007,772.817	1,075,086.454
21+50.00	40.00' Lt.	2,007,810.061	1,075,102.846
21+83.62	2.91' Lt.	2,007,787.508	1,075,053.075
21+86.49	40.00' Rt.	2,007,827.048	1,075,069.978
300+29.51	28.38' Lt.	2,007,803.346	1,075,115.563
300+41.36	1.67' Rt.	2,007,784.408	1,075,141.882
300+42.00	26.12' Lt.	2,007,808.452	1,075,127.944
300+62.53	27.85' Rt.	2,007,772.118	1,075,172.787
300+78.26	28.77' Rt.	2,007,778.261	1,075,186.279
300+79.18	8.79' Rt.	2,007,796.462	1,075,177.992
300+87.02	0.60' Rt.	2,007,807.254	1,075,181.292
301+10.22	19.96' Lt.	2,007,835.794	1,075,194.236
301+20.00	4.69' Rt.	2,007,816.876	1,075,212.902

WILLIAM UMBDENSTOCK SUBDIVISION
Recorded June 3, 1958
as Document No. 991876

EXISTING R.O.W. RECORDED INFORMATION		
Parcel	Document No.	Date Recorded
0003	521242	November 17, 1942
0003	521443	November 23, 1942
0003	1157511	August 1, 1962
----	250627	December 29, 1924
----	521242	November 17, 1942
----	521446	November 23, 1942
----	991876	June 3, 1958
----	1157511	August 1, 1962

LEGEND

SECTION CORNER: 9/10/16/15

QUARTER SECTION CORNER: 16/15

SECTION LINE: ---

QUARTER SECTION LINE: ---

PLATTED LOT LINE: ---

PROPERTY (DEED) LINE: ---

APL: ---

APPARENT PROPERTY LINE: ---

EXISTING CENTER LINE: ---

PROPOSED CENTER LINE: ---

EXISTING RIGHT OF WAY LINE: ---

PROPOSED RIGHT OF WAY LINE: ---

EXISTING EASEMENT: ---

PROPOSED EASEMENT: ---

EXISTING ACCESS CONTROL LINE: ---

PROPOSED ACCESS CONTROL LINE: ---

MEASURED DIMENSION: 120.32'

COMPUTED DIMENSION: 129.32'(Comp.)

RECORD DIMENSION: (129.32')

EXISTING BUILDING: [Hatched Box]

Scale: 1"=10'

Bearings and Coordinates are referenced to the Illinois Coordinate System NAD 83(2011) East Zone.

- IRON PIPE OR ROD FOUND
- ⊕ "MAG" NAIL SET
- + CUT CROSS FOUND OR SET
- 5/8" REBAR SET
- THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH IRON ROD FLUSH WITH GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- BT1 THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONUMENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- STAKING OF PROPOSED RIGHT OF WAY. SET DIVISION OF HIGHWAYS SURVEY MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION DATA AND SURVEYORS REGISTRATION NUMBER.
- M STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS. BURIED 5/8 INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- ⊙ PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)
- RIGHT OF WAY STAKING PROPOSED TO BE SET.

STATE OF ILLINOIS }
COUNTY OF LAKE }
THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N., RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND ESTABLISHED ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED. MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.
DATED AT LAKE VILLA, ILLINOIS THIS ____ DAY OF ____ 20__ A.D.

PRESIDENT
ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016
THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.
All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.
All measured and computed distances are grid not ground.
To obtain ground distances, divide grid distances shown by the combined factor of 0.9999548166.

PROJECT COORDINATES Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
20+48.80	40.00' Rt.	2,007,760.775	1,075,192.842
20+54.67	40.00' Rt.	2,007,763.722	1,075,187.666
20+54.76	0.01' Rt.	2,007,728.991	1,075,167.840

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371

**PLAT OF HIGHWAYS
LAKE COUNTY
DIVISION OF TRANSPORTATION
OLD McHENRY ROAD (COUNTY HIGHWAY #32)**

LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION 20+00 TO STATION 22+00
STATION 300+00.00 TO STATION 302+00
SCALE: 1"=10' SHEET 6 OF 16

LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

SEE SHEET 5

REVISION DATE

REVISION

MADE BY


PARCEL NUMBER	TOTAL HOLDINGS ACRES	PART TAKEN ACRES	AREA IN EXISTING R.O.W. ACRES	REMAINDER AREA ACRES	EASEMENT AREA		EASEMENT PURPOSE	PERMANENT INDEX NUMBER
					ACRES	SQUARE FEET		
0009 0009T.E.	0.508	0.073	0.071	0.435	0.012	N/A	Construction Purposes	15-30-100-013
0011T.E.	0.590	N/A	N/A	0.590	0.002	66	Driveway Construction	15-30-100-012

Schedule of Ties		
Point Number □	Tie to point	Tie Distance (feet)
1	T1 T2 T3	
2	T1 T2 T3	

WILLIAM
UMB DENSTOCK
SUBDIVISION
FIRST ADDITION
Recorded March 25, 1965
as Document No. 1257888

PROJECT COORDINATES			
Illinois Coordinate System		NAD 83(2011) East Zone	
STATION	OFFSET	NORTH	EAST
21+94.00	40.00' Lt.	2,007,759.099	1,075,027.098
21+95.95	3.58' Lt.	2,007,792.476	1,075,041.789
21+97.89	45.00' Lt.	2,007,756.363	1,075,021.421
22+65.00	42.00' Lt.	2,007,788.097	1,074,963.375
22+65.00	45.00' Lt.	2,007,785.387	1,074,962.089
22+93.60	7.06' Lt.	2,007,831.765	1,074,952.526
23+11.82	40.00' Lt.	2,007,809.359	1,074,922.372
23+12.94	42.00' Lt.	2,007,807.996	1,074,920.538
23+81.36	40.00' Lt.	2,007,836.992	1,074,859.614
23+81.36	40.00' Rt.	2,007,910.591	1,074,890.958
24+30.02	40.00' Lt.	2,007,856.056	1,074,814.848
24+30.03	42.00' Lt.	2,007,854.221	1,074,814.053
24+62.15	6.38' Lt.	2,007,899.578	1,074,798.456
24+63.15	40.00' Lt.	2,007,869.039	1,074,784.363
24+63.21	42.00' Lt.	2,007,867.222	1,074,783.525
203+06.56	39.40' Lt.	2,007,678.522	1,074,935.475
203+10.29	6.34' Lt.	2,007,654.518	1,074,956.517
204+12.08	34.35' Lt.	2,007,739.432	1,075,017.894
204+16.19	0.75' Lt.	2,007,717.355	1,075,043.541
204+19.82	33.56' Lt.	2,007,743.893	1,075,023.933
204+37.06	31.56' Lt.	2,007,753.858	1,075,037.414

SECTION
CORNER



QUARTER
SECTION
CORNER

----	SECTION LINE
----	QUARTER SECTION LINE
----	QUARTER, QUARTER SECTION LINE
----	PLATTED LOT LINE
<u> P </u>	PROPERTY (DEED) LINE

_____APL_____	APPARENT PROPERTY LINE
_____	EXISTING CENTER LINE
_____	PROPOSED CENTER LINE
_____	EXISTING RIGHT OF WAY LINE
_____	PROPOSED RIGHT OF WAY LINE
_____	EXISTING EASEMENT
_____	PROPOSED EASEMENT
_____AC_____	EXISTING ACCESS CONTROL LINE
_____AE_____	PROPOSED ACCESS CONTROL LINE
120.32'	MEASURED DIMENSION
129.32'(Comp.)	COMPUTED DIMENSION
(129.32')	RECORD DIMENSION

EXISTING BUILDING

Bearings and Coordinates are referenced to the Illinois Coordinate System NAD 83(2011) East Zone.

O	IRON PIPE OR ROD FOUND	⊕	"MAG" NAIL SET
+	CUT CROSS FOUND OR SET	●	5/8" REBAR SET

● T1 THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH
T2 IRON ROD FLUSH WITH GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY
T3 COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.

● BT1 THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONU-
BT2 MENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO TIE
BT3 FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SUR-
VEYORS REGISTRATION NUMBER.

■ **STAKING OF PROPOSED RIGHT OF WAY.** SET DIVISION OF HIGHWAYS SURVEY MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION DATA AND SURVEYORS REGISTRATION NUMBER.

■ M **STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS.** BURIED 5/8 INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.

 PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)

☐ RIGHT OF WAY STAKING PROPOSED TO BE SET.

STATE OF ILLINOIS)
COUNTY OF LAKE)SS

THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N., RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT THE SURVEY IS ACCORDING TO THE BEST AVAILABLE MEASUREMENTS AND THAT THE MONUMENTS ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED. MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.

DATED AT LAKE VILLA, ILLINOIS THIS _____ DAY OF _____ 20__ A.D.

PRESIDENT

ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016

THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.

All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.

All measured and computed distances are grid not ground

To obtain ground distances, divide grid distances shown the combined factor of 0.9999548166.

PROJECT COORDINATES			
Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
21+07.68	39.40' Lt.	2,007,720.085	1,075,102.759
21+25.26	1.02' Rt.	2,007,763.952	1,075,106.595
21+35.82	40.00' Rt.	2,007,803.346	1,075,115.563

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371

PLAT OF HIGHWAYS LAKE COUNTY

DIVISION OF TRANSPORTATION

OLD McHENRY ROAD (COUNTY HIGHWAY #32)
LIMITS: ILLINOIS ROUTE 53 TO CLIBA ROAD LAKE COUNTY

LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.

STATION 21+00	TO STATION 26+00
STATION 202+00	TO STATION 204+80.76

STATION 202+00 TO STATION 204+89.76
SCALE: 1"=20' SHEET 7 OF 16

LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

Existing C
Old McHenry Road
Curve #1

P.I.	=	Sta. 22+15.27
Δ	=	6°39'04"
R	=	2864.77'
T	=	166.47'
L	=	332.56'
E	=	4.83'
P.C.	=	Sta. 20+48.80
P.T.	=	Sta. 23+81.36

Existing & Proposed
C Pavement
Robert Parker Coffin Road
Curve #2

P.I.	=	Sta. 203+89.10
Δ	=	7°04'10"
R	=	954.93'
T	=	58.99'
L	=	117.82'
E	=	1.82'
P.C.	=	Sta. 203+30.11
P.T.	=	Sta. 204+47.93

LOT 2

STATE OF ILLINOIS)
COUNTY OF LAKE)SS

I, PAULA J. TRIGG, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY 32 IN SAID COUNTY.

DATED THIS _____ DAY OF _____ 20____ A.D.

COUNTY ENGINEER


REVISION DATE

REVISION

MADE BY

EXISTING R.O.W. RECORDED INFORMATION		
Parcel	Document No.	Date Recorded
0009	602679	October 14, 1946
0011	521445	November 23, 1942
----	250627	December 29, 1924
----	521242	November 17, 1942
----	521444	November 23, 1942
----	521446	November 23, 1942
----	521613	November 27, 1942
----	1260604	April 23, 1965

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.



REVISION DATE

REVISION

MADE BY

LEGEND

SECTION CORNER

QUARTER SECTION CORNER

SECTION LINE

QUARTER SECTION LINE

QUARTER SECTION LINE

PLATTED LOT LINE

PROPERTY (DEED) LINE

APL

APPARENT PROPERTY LINE

EXISTING CENTER LINE

PROPOSED CENTER LINE

EXISTING RIGHT OF WAY LINE

PROPOSED RIGHT OF WAY LINE

EXISTING EASEMENT

PROPOSED EASEMENT

EXISTING ACCESS CONTROL LINE

PROPOSED ACCESS CONTROL LINE

MEASURED DIMENSION

COMPUTED DIMENSION

RECORD DIMENSION

EXISTING BUILDING

SCALE: 1"=20'

Bearings and Coordinates are referenced to the Illinois Coordinate System NAD 83(2011) East Zone.

STATE OF ILLINOIS }
COUNTY OF LAKE }SS
I, PAULA J. TRIGG, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY 32 IN SAID COUNTY.

DATED THIS ____ DAY OF ____ 20__ A.D.

COUNTY ENGINEER

PROJECT COORDINATES			
Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
23+81.36	40.00' Rt.	2,007,910.591	1,074,890.958
23+81.36	45.00' Rt.	2,007,915.191	1,074,892.918
24+25.00	45.00' Rt.	2,007,932.291	1,074,852.767
24+30.96	65.00' Rt.	2,007,953.026	1,074,855.122
24+40.28	40.00' Rt.	2,007,933.678	1,074,836.750

EXISTING R.O.W. RECORDED INFORMATION		
Parcel	Document No.	Date Recorded
0010	521446	November 23, 1942
----	521242	November 17, 1942
----	521445	November 23, 1942
----	521446	November 23, 1942
----	602679	October 14, 1946

- IRON PIPE OR ROD FOUND
- ⊕ "MAG" NAIL SET
- + CUT CROSS FOUND OR SET
- 5/8" REBAR SET
- T1 THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH IRON ROD FLUSH WITH GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- BT1 THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONUMENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- STAKING OF PROPOSED RIGHT OF WAY. SET DIVISION OF HIGHWAYS SURVEY MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION DATA AND SURVEYORS REGISTRATION NUMBER.
- M STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS. BURIED 5/8 INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- ⊙ PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)
- RIGHT OF WAY STAKING PROPOSED TO BE SET.

STATE OF ILLINOIS }
COUNTY OF LAKE }SS
THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N., RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND ESTABLISHED ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED. MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.

DATED AT LAKE VILLA, ILLINOIS THIS ____ DAY OF ____ 20__ A.D.

PRESIDENT
ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016
THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.
All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.
All measured and computed distances are grid not ground.
To obtain ground distances, divide grid distances shown by the combined factor of 0.9999548166.

PROJECT COORDINATES			
Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
22+59.26	40.00' Rt.	2,007,859.667	1,075,003.799
23+35.00	40.00' Rt.	2,007,891.823	1,074,934.056
23+35.00	45.00' Rt.	2,007,896.391	1,074,936.090
23+81.36	40.00' Rt.	2,007,836.992	1,074,859.614

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371

PLAT OF HIGHWAYS
LAKE COUNTY

DIVISION OF TRANSPORTATION

OLD McHENRY ROAD (COUNTY HIGHWAY #32)

LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION 22+00 TO STATION 25+00
SCALE: 1"=20' SHEET 8 OF 16

LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.

STATE OF ILLINOIS }
COUNTY OF LAKE }SS

I, PAULA J. TRIGG, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY 32 IN SAID COUNTY.

DATED THIS _____ DAY OF _____ 20____ A.D.

COUNTY ENGINEER


Existing \odot
Old McHenry Road
Curve #1

P.I. = Sta. 22+15.27
 Δ = 6'39"04"
R = 2864.77'
T = 166.47'
L = 332.56'
E = 4.83'
P.C. = Sta. 20+48.80
P.T. = Sta. 23+81.36


Existing \odot
Old McHenry Road
Curve #2

P.I. = Sta. 35+76.48
 Δ = 44'19"39"
R = 2203.80'
T = 897.73'
L = 1705.00'
E = 175.83'
P.C. = Sta. 26+78.75
P.T. = Sta. 43+83.75

LEGEND



SECTION
CORNER




QUARTER
SECTION
CORNER

--- SECTION LINE
--- QUARTER SECTION LINE
--- QUARTER QUARTER SECTION LINE
--- PLATTED LOT LINE
--- PROPERTY (DEED) LINE

--- APL
--- APPARENT PROPERTY LINE
--- EXISTING CENTER LINE
--- PROPOSED CENTER LINE
--- EXISTING RIGHT OF WAY LINE
--- PROPOSED RIGHT OF WAY LINE
--- EXISTING EASEMENT
--- PROPOSED EASEMENT
--- EXISTING ACCESS CONTROL LINE
--- PROPOSED ACCESS CONTROL LINE
--- MEASURED DIMENSION
--- COMPUTED DIMENSION
--- RECORD DIMENSION

129.32'(Comp.)
(129.32')

EXISTING BUILDING



SCALE: 1"=20'

Bearings and Coordinates are referenced to the
Illinois Coordinate System NAD 83(2011) East Zone.

\odot IRON PIPE OR ROD FOUND \oplus "MAG" NAIL SET
+ CUT CROSS FOUND OR SET \bullet 5/8" REBAR SET

\bullet T1 THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH
T2 IRON ROD FLUSH WITH GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY
T3 COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.

\bullet BT1 THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONU-
BT2 MENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO TIE
BT3 FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SUR-
VEYORS REGISTRATION NUMBER.

\blacksquare STAKING OF PROPOSED RIGHT OF WAY. SET DIVISION OF HIGHWAYS SURVEY
MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION
DATA AND SURVEYORS REGISTRATION NUMBER.

\blacksquare M STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS. BURIED 5/8
INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY
MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING
SURVEYORS REGISTRATION NUMBER.

\odot PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)

\square RIGHT OF WAY STAKING PROPOSED TO BE SET.

STATE OF ILLINOIS }
COUNTY OF LAKE }SS

THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS
PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE
SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N.,
RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS
TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT
THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND
ESTABLISHED ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON
AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED.
MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.

DATED AT LAKE VILLA, ILLINOIS THIS _____ DAY OF _____ 20____ A.D.

PRESIDENT

ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016

THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT
ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.

All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.
All measured and computed distances are grid not ground.
To obtain ground distances, divide grid distances shown by
the combined factor of 0.9999548166.

PROJECT COORDINATES Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
23+81.36	40.00' Lt.	2,007,836.992	1,074,859.614
23+81.36	40.00' Rt.	2,007,910.591	1,074,890.958
24+30.96	65.00' Rt.	2,007,953.026	1,074,855.122
24+40.28	40.00' Rt.	2,007,933.678	1,074,836.750

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371

PLAT OF HIGHWAYS LAKE COUNTY

DIVISION OF TRANSPORTATION

OLD McHENRY ROAD (COUNTY HIGHWAY #32)

LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION 23+00 TO STATION 27+00
SCALE: 1"=20' SHEET 9 OF 16

LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

THE LAKES OF LONG GROVE SUBDIVISION

Recorded August 30, 1977
as Document No. 1861302
Corrected by Letter of Amendment
Recorded October 27, 1977
as Document No. 1876064


PARCEL NUMBER	TOTAL HOLDINGS ACRES	PART TAKEN ACRES	AREA IN EXISTING R.O.W. ACRES	REMAINDER AREA ACRES	EASEMENT AREA ACRES	EASEMENT PURPOSE	PERMANENT INDEX NUMBER
0012T.E.	0.890	N/A	N/A	0.890	0.047	Construction Purposes	15-30-100-010

REVISION DATE

REVISION

MADE BY

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.



EXISTING R.O.W. RECORDED INFORMATION		
Parcel	Document No.	Date Recorded
0013	521612	November 27, 1942
0014	521615	November 27, 1942
----	521242	November 17, 1942
----	521446	November 23, 1942
----	521612	November 27, 1942
----	521613	November 27, 1942
----	521615	November 27, 1942

PROJECT COORDINATES Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
26+78.75	40.00' Rt.	2,008,027.118	1,074,617.347
26+78.75	45.00' Rt.	2,008,031.718	1,074,619.306
27+32.40	40.00' Rt.	2,008,048.346	1,074,569.138
27+34.19	3.81' Lt.	2,008,009.214	1,074,549.364
28+53.60	8.63' Lt.	2,008,057.488	1,074,439.688
28+51.49	40.00' Lt.	2,008,028.698	1,074,427.057
29+70.00	45.00' Rt.	2,008,160.502	1,074,364.957
29+70.00	50.00' Rt.	2,008,164.804	1,074,367.506
30+45.00	40.00' Lt.	2,008,127.400	1,074,256.614
30+45.00	45.00' Lt.	2,008,123.187	1,074,253.921
30+70.09	34.22' Lt.	2,008,146.113	1,074,238.334
31+15.00	40.00' Lt.	2,008,166.735	1,074,197.185
31+15.00	45.00' Lt.	2,008,162.610	1,074,194.360
31+52.00	40.00' Lt.	2,008,188.284	1,074,166.286
31+52.00	50.00' Lt.	2,008,180.130	1,074,160.497
31+75.00	40.00' Lt.	2,008,201.939	1,074,147.262
31+75.00	50.00' Lt.	2,008,193.846	1,074,141.389
32+30.00	40.00' Rt.	2,008,298.943	1,074,150.944
32+30.00	50.00' Rt.	2,008,306.887	1,074,157.018
34+48.47	40.00' Rt.	2,008,437.452	1,073,987.273

See Sheet 14
for Total Holdings
Parcel 0014T.E.-A & B

Existing @
Old McHenry Road
Curve #2

P.I. = Sta. 35+76.48
Δ = 44°19'39"
R = 2203.80'
T = 897.73'
L = 1705.00'
E = 175.83'
P.C. = Sta. 26+78.75
P.T. = Sta. 43+83.75

PARCEL NUMBER	TOTAL HOLDINGS ACRES	PART TAKEN ACRES	AREA IN EXISTING R.O.W. ACRES	REMAINDER AREA ACRES	EASEMENT AREA SQUARE FEET	EASEMENT PURPOSE	PERMANENT INDEX NUMBER
0013T.E.	10.657	N/A	N/A	10.657	0.094	Construction Purposes	15-30-100-004 15-30-100-006
0014T.E.-A 0014T.E.-B	13.832	N/A	N/A	13.832	T.E.-A=0.008 T.E.-B=0.005	Grading Grading	15-30-100-005 15-30-100-008

REVISION DATE


REVISION

STATE OF ILLINOIS }
COUNTY OF LAKE }SS
I, PAULA J. TRIGG, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY 32 IN SAID COUNTY.
DATED THIS _____ DAY OF _____ 20____ A.D.

COUNTY ENGINEER

THE LAKES OF LONG GROVE SUBDIVISION
Recorded August 30, 1977
as Document No. 1861302
Corrected by Letter of Amendment
Recorded October 27, 1977
as Document No. 1876064

LEGEND



- IRON PIPE OR ROD FOUND
- CUT CROSS FOUND OR SET
- THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH IRON ROD FLUSH WITH GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONUMENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- STAKING OF PROPOSED RIGHT OF WAY. SET DIVISION OF HIGHWAYS SURVEY MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION DATA AND SURVEYORS REGISTRATION NUMBER.
- STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS. BURIED 5/8 INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)
- RIGHT OF WAY STAKING PROPOSED TO BE SET.

STATE OF ILLINOIS }
COUNTY OF LAKE }SS
THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N., RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND ESTABLISHED ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED. MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.
DATED AT LAKE VILLA, ILLINOIS THIS _____ DAY OF _____ 20____ A.D.

PROJECT COORDINATES Illinois Coordinate System NAD 83(2011) East Zone			
STATION	OFFSET	NORTH	EAST
26+53.69	45.00' Rt.	2,008,021.900	1,074,642.360
26+54.00	40.00' Rt.	2,008,017.421	1,074,640.115
26+56.74	4.04' Lt.	2,007,977.974	1,074,620.340
26+78.75	40.00' Lt.	2,007,953.518	1,074,586.002

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371

PLAT OF HIGHWAYS
LAKE COUNTY
DIVISION OF TRANSPORTATION
OLD McHENRY ROAD (COUNTY HIGHWAY #32)
LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION 26+00 TO STATION 35+00
SCALE: 1"=40' SHEET 10 OF 16
LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.


SURVEY AND DIVISION
Recorded November 23, 1930
as Document No. 362197
Corrected by Certificate of Correction
Recorded February 26, 1931
as Document No. 365601
TRACT C

OLD McHENRY ROAD
R.O.W. Old McHenry
Road as Dec. 521242
N60°16'50"W
6.12'(6.11')

COUNTY HIGHWAY #32
Existing R.O.W. Line

**FIRE STATION
SUBDIVISION**
Recorded July 10, 1980
as Document No. 2067613

1



THE LAKES OF LONG GROVE SUBDIVISION
Recorded August 30, 1977
as Document No. 1861302
Corrected by Letter of Amendment
Recorded October 27, 1977
as Document No. 1876064

ARCHER LOTS SUBDIVISION
Recorded December 12, 2011
as Document No. 6798242

**TOTAL HOLDINGS
PARCEL 0001T.E.**

FAIRFIELD VILLAGE
Recorded January 4, 1980
as Document No. 2042549
Corrected by Certificate of Correction
Recorded April 7, 1980
as Document No. 2055570

STATE OF ILLINOIS }
COUNTY OF LAKE }SS
I, PAULA J. TRIGG, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY
CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF
THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY 32 IN
SAID COUNTY.
DATED THIS ____ DAY OF ____ 20__ A.D.

COUNTY ENGINEER

REVISION DATE

REVISION

MADE BY

LEGEND

SECTION CORNER: 9 10 16 15
QUARTER SECTION CORNER: 16 15

SECTION LINE
QUARTER SECTION LINE
QUARTER QUARTER SECTION LINE
PLATTED LOT LINE
PROPERTY (DEED) LINE

APL
APPARENT PROPERTY LINE
EXISTING CENTER LINE
PROPOSED CENTER LINE
EXISTING RIGHT OF WAY LINE
PROPOSED RIGHT OF WAY LINE
EXISTING EASEMENT
PROPOSED EASEMENT
EXISTING ACCESS CONTROL LINE
PROPOSED ACCESS CONTROL LINE
MEASURED DIMENSION
COMPUTED DIMENSION
RECORD DIMENSION

EXISTING BUILDING

0 30' 60'
SCALE: 1"=30'

Bearings and Coordinates are referenced to the Illinois Coordinate System NAD 83(2011) East Zone.

- IRON PIPE OR ROD FOUND
 - + CUT CROSS FOUND OR SET
 - T1 THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH IRON ROD FLUSH WITH GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
 - BT1 THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONUMENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
 - STAKING OF PROPOSED RIGHT OF WAY. SET DIVISION OF HIGHWAYS SURVEY MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION DATA AND SURVEYORS REGISTRATION NUMBER.
 - M STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS. BURIED 5/8 INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
 - ⊙ PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)
 - RIGHT OF WAY STAKING PROPOSED TO BE SET.
 - 2 STATE OF ILLINOIS }
COUNTY OF LAKE }SS
- THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N., RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND ESTABLISHED ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED. MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.
- DATED AT LAKE VILLA, ILLINOIS THIS ____ DAY OF ____ 20__ A.D.

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371

ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016

THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.

All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.
All measured and computed distances are grid not ground.
To obtain ground distances, divide grid distances shown by the combined factor of 0.9999548166.



**PLAT OF HIGHWAYS
LAKE COUNTY
DIVISION OF TRANSPORTATION**
OLD McHENRY ROAD (COUNTY HIGHWAY #32)
LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION NONE TO STATION
SCALE: 1"=30' SHEET 11 OF 16

LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.

THE LAKES OF LONG GROVE SUBDIVISION
Recorded August 30, 1977
as Document No. 1861302
Corrected by Letter of Amendment
Recorded October 27, 1977
as Document No. 1876064

LEGEND



Bearings and Coordinates are referenced to the Illinois Coordinate System NAD 83(2011) East Zone.

- SECTION LINE
- QUARTER SECTION LINE
- QUARTER, QUARTER SECTION LINE
- PLATTED LOT LINE
- PROPERTY (DEED) LINE
- APL
- APPARENT PROPERTY LINE
- EXISTING CENTER LINE
- PROPOSED CENTER LINE
- EXISTING RIGHT OF WAY LINE
- PROPOSED RIGHT OF WAY LINE
- EXISTING EASEMENT
- PROPOSED EASEMENT
- EXISTING ACCESS CONTROL LINE
- PROPOSED ACCESS CONTROL LINE
- MEASURED DIMENSION
- COMPUTED DIMENSION
- RECORD DIMENSION
- EXISTING BUILDING

- IRON PIPE OR ROD FOUND
- CUT CROSS FOUND OR SET
- T1
- T2
- T3
- BT1
- BT2
- BT3
- STAKING OF PROPOSED RIGHT OF WAY
- STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS
- PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)
- RIGHT OF WAY STAKING PROPOSED TO BE SET

THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N., RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND ESTABLISHED ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED. MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.

DATED AT LAKE VILLA, ILLINOIS THIS ____ DAY OF ____ 20__ A.D.

ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016
THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.
All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.
All measured and computed distances are grid not ground.
To obtain ground distances, divide grid distances shown by the combined factor of 0.99999548166.

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371

PLAT OF HIGHWAYS
LAKE COUNTY
DIVISION OF TRANSPORTATION
OLD McHENRY ROAD (COUNTY HIGHWAY #32)
LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION NONE TO STATION
SCALE: 1"=30' SHEET 12 OF 16

LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

STATE OF ILLINOIS }
COUNTY OF LAKE }SS
I, PAULA J. TRIGG, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY 32 IN SAID COUNTY.
DATED THIS ____ DAY OF ____ 20__ A.D.

COUNTY ENGINEER

RED OAKS
Recorded December 26, 1986
as Document No. 2519282
Corrected by Certificates of Correction
Recorded July 16, 1987
as Document No. 2590825
and Recorded July 27, 1987
as Document No. 2594571



REVISION DATE

REVISION


MADE BY

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.

LEGEND



_____ SECTION LINE
 _____ QUARTER SECTION LINE
 _____ QUARTER, QUARTER SECTION LINE
 _____ PLATTED LOT LINE
 _____ P PROPERTY (DEED) LINE

— APL —	APPARENT PROPERTY LINE	
— — —	EXISTING CENTER LINE	
— — —	PROPOSED CENTER LINE	
— — —	EXISTING RIGHT OF WAY LINE	
— — —	PROPOSED RIGHT OF WAY LINE	
— — —	EXISTING EASEMENT	
— — —	PROPOSED EASEMENT	
— AC —	EXISTING ACCESS CONTROL LINE	
— AC —	PROPOSED ACCESS CONTROL LINE	
120.32'	MEASURED DIMENSION	
129.32'(Comp.)	COMPUTED DIMENSION	
(129.32')	RECORD DIMENSION	

EXISTING BUILDING



SCALE: 1"=30'

Bearings and Coordinates are referenced to the
Illinois Coordinate System NAD 83(2011) East Zone.

○	IRON PIPE OR ROD FOUND	⊕	"MAG" NAIL SET
+	CUT CROSS FOUND OR SET	●	5/8" REBAR SET

● T1 THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH
T2 IRON ROD FLUSH WITH GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY
T3 COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.

● BT1 THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONU-
BT2 MENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO THE
BT3 FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SUR-
VEYORS REGISTRATION NUMBER.

■ **STAKING OF PROPOSED RIGHT OF WAY.** SET DIVISION OF HIGHWAYS SURVEY MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION DATA AND SURVEYORS REGISTRATION NUMBER.

■ M **STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS.** BURIED 5/8 INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.

 PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)

☐ RIGHT OF WAY STAKING PROPOSED TO BE SET.

STATE OF ILLINOIS)
COUNTY OF LAKE)SS

THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N., RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND ESTABLISHED FOR THE PERMANENT RECORD AND ACCURACY SHOWN THEREON, AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED. MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.

DATED AT LAKE VILLA, ILLINOIS THIS _____ DAY OF _____ 20__ A.D.

PRESIDENT
ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016

THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.

All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.
All measured and computed distances are grid not ground.
To obtain ground distances, divide grid distances shown by
the combined factor of 0.9999548166.

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371

PLAT OF HIGHWAYS
LAKE COUNTY
DIVISION OF TRANSPORTATION

OLD McHENRY ROAD (COUNTY HIGHWAY #32)
LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION NONE TO STATION
SCALE: 1"=30' SHEET 13 OF 16

LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

STATE OF ILLINOIS)
COUNTY OF LAKE)SS

I, PAULA J. TRIGG, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY 32 IN SAID COUNTY.

DATED THIS _____ DAY OF _____ 20__ A.D.

COUNTY ENGINEER

REVISION DATE



REVISION

MADE BY

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.


GRAY'S SUBDIVISION
Recorded April 4, 1972
as Document No. 1551128

LEGEND



SECTION LINE
QUARTER SECTION LINE
QUARTER, QUARTER SECTION LINE
PLATTED LOT LINE
PROPERTY (DEED) LINE

APL APPARENT PROPERTY LINE
EXISTING CENTER LINE
PROPOSED CENTER LINE
EXISTING RIGHT OF WAY LINE
PROPOSED RIGHT OF WAY LINE
EXISTING EASEMENT
PROPOSED EASEMENT
EXISTING ACCESS CONTROL LINE
PROPOSED ACCESS CONTROL LINE
MEASURED DIMENSION
120.32'
129.32'(Comp.)
(129.32')



EXISTING BUILDING



Bearings and Coordinates are referenced to the
Illinois Coordinate System NAD 83(2011) East Zone.

○ IRON PIPE OR ROD FOUND ⊕ "MAG" NAIL SET
+ CUT CROSS FOUND OR SET ● 5/8" REBAR SET

● T1 THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH
T2 IRON ROD FLUSH WITH GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY
T3 COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.

● BT1 THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONU-
BT2 MENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO TIE
BT3 FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SUR-
VEYORS REGISTRATION NUMBER.

■ STAKING OF PROPOSED RIGHT OF WAY. SET DIVISION OF HIGHWAYS SURVEY
MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION
DATA AND SURVEYORS REGISTRATION NUMBER.

■ M STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS. BURIED 5/8
INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY
MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING
SURVEYORS REGISTRATION NUMBER.

⊙ PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)

□ RIGHT OF WAY STAKING PROPOSED TO BE SET.

STATE OF ILLINOIS }
COUNTY OF LAKE }SS

THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS
PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE
SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N.,
RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS
TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT
THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND
ESTABLISHED ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON
AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED.
MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.

DATED AT LAKE VILLA, ILLINOIS THIS ____ DAY OF _____ 20__ A.D.

PRESIDENT

ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016

THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT
ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.

All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.
All measured and computed distances are grid not ground.
To obtain ground distances, divide grid distances shown by
the combined factor of 0.9999548166.

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371

PLAT OF HIGHWAYS
LAKE COUNTY
DIVISION OF TRANSPORTATION
OLD McHENRY ROAD (COUNTY HIGHWAY #32)

LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION NONE TO STATION
SCALE: 1"=60' SHEET 14 OF 16


LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

STATE OF ILLINOIS }
COUNTY OF LAKE }SS

I, PAULA J. TRIGG, COUNTY ENGINEER OF LAKE COUNTY, ILLINOIS, DO HEREBY
CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF
THE SURVEY MADE UNDER MY DIRECTION OF PART OF COUNTY HIGHWAY 32 IN
SAID COUNTY.

DATED THIS ____ DAY OF _____ 20__ A.D.

COUNTY ENGINEER



TOTAL HOLDINGS
PARCEL 0014T.E.-A & B

Proposed Temporary Easement Line

0014T.E.-A

0014T.E.-B

Proposed Temporary Easement Line

0013T.E.

TOTAL HOLDINGS
PARCEL 0013T.E.

COUNTY HIGHWAY #32

N66°14'37"W
77.55'

N26°48'30"E
43.84'

N66°14'37"W
77.55'

N26°48'30"E
43.84'

Proposed Temporary Easement Line

0012T.E.

(73.89')

12

THE LAKES OF LONG
GROVE SUBDIVISION
Recorded August 30, 1977
as Document No. 1861302
Corrected by Letter of Amendment
Recorded October 27, 1977
as Document No. 1876064

E. Line NW 1/4 NW 1/4
Sec. 30-43-11

S0°05'19"W
-657.37'-

W. Line NE 1/4 NW 1/4
Sec. 30-43-11

(310.0')


13

MADE BY


REVISION

REVISION DATE

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.



LEGEND



- IRON PIPE OR ROD FOUND
- CUT CROSS FOUND OR SET
- THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH IRON ROD FLUSH WITH GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONUMENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- STAKING OF PROPOSED RIGHT OF WAY. SET DIVISION OF HIGHWAYS SURVEY MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION DATA AND SURVEYORS REGISTRATION NUMBER.
- STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS. BURIED 5/8 INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)
- RIGHT OF WAY STAKING PROPOSED TO BE SET.

THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N., RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND ESTABLISHED ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED. MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.

DATED AT LAKE VILLA, ILLINOIS THIS ____ DAY OF _____ 20__ A.D.

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371

ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016


THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.

All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.
All measured and computed distances are grid not ground.
To obtain ground distances, divide grid distances shown by the combined factor of 0.9999548166.

PLAT OF HIGHWAYS
LAKE COUNTY
DIVISION OF TRANSPORTATION
OLD McHENRY ROAD (COUNTY HIGHWAY #32)
LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION 7+59.80 TO STATION 21+24.56
STATION 100+00.00 TO STATION 104+14.66
STATION 300+00.00 TO STATION 303+90.21
SCALE: 1"=60' SHEET 15 OF 16

LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

PART OF THE NW 1/4 OF SEC. 30, TWP. 43 N., R. 11 E. OF THE 3RD. P.M., IN LAKE COUNTY, ILLINOIS.



LEGEND

SECTION CORNER 16 15 QUARTER SECTION CORNER

SECTION LINE
QUARTER SECTION LINE
QUARTER, QUARTER SECTION LINE
PLATTED LOT LINE
PROPERTY (DEED) LINE

APL APPARENT PROPERTY LINE
EXISTING CENTER LINE
PROPOSED CENTER LINE
EXISTING RIGHT OF WAY LINE
PROPOSED RIGHT OF WAY LINE
EXISTING EASEMENT
PROPOSED EASEMENT
EXISTING ACCESS CONTROL LINE
PROPOSED ACCESS CONTROL LINE

MEASURED DIMENSION
COMPUTED DIMENSION
RECORD DIMENSION

EXISTING BUILDING

SCALE: 1"=100'

Bearings and Coordinates are referenced to the Illinois Coordinate System NAD 83(2011) East Zone.

- IRON PIPE OR ROD FOUND
- CUT CROSS FOUND OR SET
- THESE STAKES REFERENCE FOUND OR SET MONUMENTATION. SET 5/8 INCH IRON ROD FLUSH WITH GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- BT1 BT2 BT3 THESE STAKES, IN CULTIVATED AREAS, REFERENCE FOUND OR SET MONUMENTATION. BURIED 5/8 INCH IRON ROD 20 INCHES BELOW GROUND TO TIE FOUND IRON STAKE. IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- STAKING OF PROPOSED RIGHT OF WAY. SET DIVISION OF HIGHWAYS SURVEY MARKER TO MONUMENT THE POSITION SHOWN. IDENTIFIED BY INSCRIPTION DATA AND SURVEYORS REGISTRATION NUMBER.
- M STAKING OF PROPOSED RIGHT OF WAY IN CULTIVATED AREAS. BURIED 5/8 INCH METAL ROD 20 INCHES BELOW GROUND TO MARK FUTURE SURVEY MARKER POSITION IDENTIFIED BY COLORED PLASTIC CAP BEARING SURVEYORS REGISTRATION NUMBER.
- PERMANENT SURVEY MARKER, I.D.O.T STD 2135 (TO BE SET BY OTHERS)
- RIGHT OF WAY STAKING PROPOSED TO BE SET.

STATE OF ILLINOIS }
COUNTY OF LAKE }
THIS IS TO CERTIFY THAT WE, JORGENSEN & ASSOCIATES, INC., AN ILLINOIS PROFESSIONAL DESIGN FIRM LAND SURVEYING CORPORATION, NUMBER 184-2771, HAVE SURVEYED THE PLAT OF HIGHWAYS SHOWN HEREON IN SECTION 30, TOWNSHIP 43N., RANGE 11E., OF THE THIRD PRINCIPAL MERIDIAN, LAKE COUNTY, THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND BELIEF, THAT THE PLAT CORRECTLY REPRESENTS SAID SURVEY, THAT ALL MONUMENTS FOUND AND ESTABLISHED ARE OF PERMANENT QUALITY AND OCCUPY THE POSITIONS SHOWN THEREON AND THAT THE MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED. MADE FOR THE LAKE COUNTY DIVISION OF TRANSPORTATION, STATE OF ILLINOIS.

DATED AT LAKE VILLA, ILLINOIS THIS ____ DAY OF _____ 20__ A.D.

PRESIDENT
ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 35-2797
LICENSE EXPIRATION DATE: NOVEMBER 30, 2016
THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.
All dimensions are measured unless otherwise specified.
Areas shown on this plat are ground.
All measured and computed distances are grid not ground.
To obtain ground distances, divide grid distances shown by the combined factor of 0.9999548166.

JORGENSEN & ASSOCIATES, INC.
120 PARK AVENUE
LAKE VILLA, ILLINOIS 60046
(847) 356-3371


PLAT OF HIGHWAYS
LAKE COUNTY
DIVISION OF TRANSPORTATION
OLD McHENRY ROAD (COUNTY HIGHWAY #32)
LIMITS: ILLINOIS ROUTE 53 TO CUBA ROAD LAKE COUNTY
SECTION: 11-00083-09-RS JOB NO.
STATION 20+00 TO STATION 48+00.00
STATION 200+00.00 TO STATION 204+89.76
SCALE: 1"=100' SHEET 16 OF 16

LAKE COUNTY DIVISION OF TRANSPORTATION
600 WEST WINCHESTER ROAD
LIBERTYVILLE, ILLINOIS 60048

Image# 048546810006 Type: PLH
Recorded: 03/23/2012 at 02:13:44 PM
Receipt#: 2012-00016992
Page 1 of 6

Lake County IL Recorder
Mary Ellen Vanderventer Recorder
File **6832994**

6832994
3-23-12




```
SECTION LINE
QUARTER SECTION LINE
QUARTER, QUARTER SECTION LINE
PLATTED LOT LINES
PROPERTY (DEED) LINE
APPARENT PROPERTY LINE
CENTERLINE
EXISTING RIGHT OF WAY LINE
PROPOSED RIGHT OF WAY LINE
PROPOSED EASEMENT
MEASURED DIMENSION
COMPUTED DIMENSION
RECORDED DIMENSION
RIGHT OF WAY STAKING (TO BE SET)
POINT OF COMMENCEMENT
POINT OF BEGINNING
```

NOTE: Bearings are referenced to Minois State Plane East Zone
NAD83 (CORS). Grid distances and coordinates are shown.
The average grid factor for the project is 0.999946.

Handmaids of the Precious Blood
a New Mexico Not-For-Profit Corporation
P.I.N. 02-30-400-006

Centerline
Curve-1
R=8000.00'
L=216.47'
Chd Brg=N 88° 41'15"E
Chd Dist=216.46'



PROPOSED PETITE LAKE RD. CENTERLINE INFORMATION		
STATION	STATE PLANE NORTHING	STATE PLANE EASTING
P.O.T. 29+67.85	2099360.878	1045375.819
P.C. 40+54.50	2099371.068	1046462.423
P.I. 41+62.75	2099372.083	1046570.660
P.R.C. 42+70.97	2099376.026	1046678.830
P.I. 44+00.35	2099380.739	1046808.121
P.T. 45+29.30	2099381.268	1046937.496
P.C. 53+37.06	2099384.575	1047744.844
P.I. 56+77.30	2099385.968	1048085.081
P.T. 60-02.61	2099553.861	1048381.011
P.O.T. 78-68.09	2100474.389	1050003.551

STATE OF ILLINOIS)
) S.S.
COUNTY OF LAKE)

I, MARTIN G. BUEHLER, COUNTY ENGINEER OF THE COUNTY AFORESAID,
DO HEREBY CERTIFY THAT THE PLAT HEREON IS A TRUE AND CORRECT
REPRESENTATION OF THE SURVEY MADE UNDER MY DIRECTION OF
PART OF COUNTY HIGHWAY 51 IN SAID COUNTY.

DATED THIS 13th DAY OF March, A.D. 2012.

Yard & Butler

[illegible]

THIS IS TO CERTIFY THAT WE, LAKE COUNTY DIVISION OF TRANSPORTATION
HAVE SURVEYED THE PLAT OF HIGHWAY SHOWN HEREON, THAT THE SURVEY
IS TRUE AND COMPLETE AS SHOWN TO THE BEST OF MY KNOWLEDGE AND
BELIEF.

DATED AT LIBERTYVILLE, ILLINOIS THIS 13th DAY OF MARCH A.D. 2012.

ILLINOIS PROFESSIONAL LAND SURVEYOR NO. 035-2848
LICENSE EXPIRATION DATE: 11/30/2012

THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT
ILLINOIS MINIMUM STANDARDS FOR A BOUNDARY SURVEY.



R.O.W. staking 3/12 PLAT OF HIGHWAYS COUNTY HIGHWAY NO. 51 - PETITE LAKE ROAD	
SECTION:	181
PROJECT:	00-00181-03-RS
STATION:	29+67.83 TO 78+68.08
SCALE:	1" = 50'
DRAWN BY:	SWH 5/01/03
COMP. FILE:	Revised POHsheet1
REVISIONS:	9/13/05, 3/15/06, 4/11/06, 6/21/07
SHEET	NO. 1 OF 5